ISO/IEC 14763-2:2019-12 (E)

Information technology - Implementation and o peration of customer premises cabling - Part 2: Planning and installation

Contents

Page

FOREWORD 9
INTRODUCTION 11
1 Scope 13
2 Normative references 14
3 Terms, definitions and abbreviated terms 15
3.1 Terms and definitions 15
3.2 Abbreviated terms 20
3.3 Conventions 21
4 Conformance 21
5 Specification of installations 21
5.1 General 21
5.2 Installation specification 22
5.2.1 Requirements 22
5.2.2 Recommendations 23
5.3 Technical specification 24
5.3.1 General 24
5.3.2 Notification of hazards 24
5.3.3 Security requirements 25
5.3.4 Performance and configuration – Requirements 25
5.3.5 Environmental conditions 27
5.4 Scope of work 28
5.4.1 Pre-installation 28
5.4.2 Installation 29
5.4.3 Post-installation 30
5.5 Quality assurance 30
6 Quality planning 30
6.1 Quality plan 30
6.2 Specification of cabling components 31
6.3 Sampling 32
6.3.1 Balanced cabling 32
6.3.2 Optical fibre cabling 34
6.4 Treatment of marginal results 36
6.4.1 Balanced cabling 36
6.4.2 Optical fibre cabling 36
6.5 Treatment of non-compliant results 36
6.6 Change control 36

7 Installation planning 36
7.1 General 36
7.2 Safety 37
7.2.1 General 37
7.2.2 Low voltage power supply cabling 37
7.2.3 Telecommunications cables fire performance 37
7.2.4 Optical fibre cabling 37
7.2.5 Transmission and terminal equipment 37
7.3 Environment 37
7.4 Points of electrical contact 38
7.5 External service provision 38
7.5.1 Requirements 38
7.5.2 Recommendations 38
7.6 Pathways and pathway systems 38
7.6.1 General 38
7.6.2 Inside buildings 42
7.6.3 Outside buildings 49
7.7 Spaces 61
7.7.1 Requirements 61
7.7.2 Recommendations 66
7.8 Functional elements 68
7.8.1 Requirements 68
7.8.2 Recommendations 70
7.9 Segregation of telecommunications cabling and power supply cabling inside buildings 70
7.9.1 General 70
7.9.2 Requirements 72
7.9.3 Recommendations 78
7.10 Segregation of underground telecommunications cabling and power supply cabling outside buildings 78
7.10.1 General 78
7.10.2 Power supply cabling ≤ AC 1 000 V RMS or DC 1 500 V 78
7.10.3 Power supply cabling > AC 1 000 V RMS or DC 1 500 V 79
7.10.4 Earthing systems 80
7.10.5 Other infrastructures 81
7.11 Segregation of aerial telecommunications cabling 82
7.11.1 General 82
7.11.2 Overhead power supply infrastructures 82
7.11.3 Sharing of infrastructures carrying ≤ 1 000 V AC (1 500 V DC) 84
7.11.4 Sharing of infrastructures carrying > 1 000 V AC (1 500 V DC) 86
7.12 Planning for repair 86
7.13 Cabling – Requirements 87
7.13.1 General 87
7.13.2 Unscreened cabling 87
7.13.3 Screened cabling 87
7.13.4 Optical fibre cabling 87
7.14 Planning and assessment of cabling in support of remote powering objectives 88
7.14.1 General 88
7.14.2 Remote powering installations of Category RP3 88
7.14.3 Connecting hardware 92

8 Installation practices 93
8.1 General 93
8.2 Safety 93
8.2.1 General 93
8.2.2 Power supply cabling 93
8.2.3 Telecommunications cables fire performance 93
8.2.4 Optical fibre cabling 93
8.2.5 Guards and signs 94
8.2.6 Enclosed spaces 94
8.2.7 Maintenance holes 94
8.2.8 Closures 94
8.3 Environment 94
8.3.1 Storage 94
8.3.2 Installation – Requirements 94
8.4 Component inspection and testing – Requirements 94
8.5 Pathways 95
8.5.1 Requirements 95
8.5.2 Recommendations 96
8.6 Spaces 96
8.6.1 Requirements 96
8.6.2 Recommendations 97
8.7 Pathway system installation 97
8.7.1 General 97
8.7.2 Inside buildings 98
8.7.3 Outside buildings 98
8.8 Closure installation 98
8.9 Cable installation 99
8.9.1 Cable installation within pathway systems 99
8.9.2 Inside buildings 100
8.9.3 Cable installation in maintenance holes 101
8.9.4 Cable installation within closures – Requirements 102
8.10 Jointing and terminating of cables 102
8.10.1 Requirements 102
8.10.2 Balanced cabling 103
8.10.3 Screened balanced cabling 103
8.10.4 Optical fibre cabling 103
8.11 Cords and jumpers 103
8.12 Surge protective devices 103
8.13 Acceptance 104
8.13.1 Inspection 104
8.13.2 Testing 104
9 Documentation and administration 104
9.1 Symbols and preparation of documents 104
9.1.1 Requirements 104
9.1.2 Recommendations 104
9.2 Administration 104
9.2.1 General 104
9.2.2 Administration system 105
9.2.3 Identifiers – Requirements 109

9.2.4 Component labelling 109
9.2.5 Records 112
9.2.6 Cable administration system 116
9.2.7 Reports 119
10 Testing 119
10.1 General 119
10.1.1 Links and permanent links 119
10.1.2 Channels 120
10.1.3 Cabling interface adapters 121
10.1.4 Calibration 121
10.1.5 Equipment protection 121
10.1.6 Measurement conditions 122
10.2 Test procedures for balanced cabling 122
10.2.1 General 122
10.2.2 Measurement of length-related parameters 122
10.2.3 Treatment of marginal test results 122
10.2.4 Treatment of unacceptable test results 122
10.2.5 Test result format 122
10.2.6 Test result documentation 123
10.3 Test procedures for optical fibre cabling 123
10.3.1 General 123
10.3.2 Treatment of unacceptable test results 123
10.3.3 Test result documentation 124
11 Inspection 124
11.1 General 124
11.2 Inspection Level 1 124
11.3 Inspection Level 2 125
11.4 Inspection Level 3 125
11.5 Inspection documentation – Requirements 125
12 Operation 126
12.1 Connection of equipment 126
12.2 Standard operating procedure 126
12.2.1 Requirements 126
12.2.2 Recommendations 126
12.3 Cords and jumpers 126
12.4 Optical fibre adapters 126
13 Maintenance 127
13.1 Approaches to maintenance 127
13.1.1 General 127
13.1.2 Requirements 127
13.2 Maintenance procedures 127
13.2.1 Requirements 127
13.2.2 Recommendations 127
14 Repair 128
Annex A (normative) Optical fibre polarity maintenance: connecting hardware for multiple optical fibres 129
Annex B (normative) Common infrastructures within multi-tenant premises 143
Annex C (normative) Cabling in accordance with ISO/IEC 11801-2 151

Annex D (normative) Cabling in accordance with ISO/IEC 11801-3 153
Annex E (normative) Cabling in accordance with ISO/IEC 11801-4 156
Annex F (normative) Cabling in accordance with ISO/IEC 11801-5 162
Annex G (normative) Cabling in accordance with ISO/IEC 11801-6 166
Annex H (informative) Equipment accommodation environments 168
Annex I (normative) Information for remote powering 169
Bibliography 173

Figure 1 – Schematic relationship between ISO/IEC 14763-2 and other relevant International Standards and Technical Reports 12
Figure 2 – Quality assurance schematic 22
Figure 3 – Conductor current for IEEE 802.3 remote powering applications 26
Figure 4 – Examples of conformant and non-conformant bend radius management 44
Figure 5 – Example of use of curved corners in pathway systems 46
Figure 6 – Example of layered cable trays with smaller width upper trays 48
Figure 7 – Example of uncovered (accessible) row of floor tiles to provide access to lower tray 48
Figure 8 – Example of cabling installations outside buildings 49
Figure 9 – Example of wind vibration damper 61
Figure 10 – Dimensions of rooms intended to contain distributors 63
Figure 11 – Process of determining cable separation 72
Figure 12 – Flowchart for cable separation calculation 75
Figure 13 – Separation of power supply and telecommunications cables without dividers 76
Figure 14 – Assumed minimum separation of power supply and telecommunications cables with dividers 77
Figure 15 – Example of cable separation distance 77
Figure 16 – Example showing the protection of underground information technology cables when located next to power supply cables 79
Figure 17 – Separation of adjacent infrastructures 83
Figure 18 – Separation distances on supporting structures 85
Figure 19 – Separation distance on supporting structures with lighting devices 85
Figure 20 – Separation of cable bundles to minimize heating 101
Figure 21 – Examples of labels indicating RP Category of remote powering installation 108
Figure 22 – Examples of cord and jumper labelling 111
Figure 23 – Cable administration database and possible linkages 117
Figure 24 – Basic cabling administration 117
Figure 25 – Examples of cabling permanent links 120
Figure 26 – Reference planes for link and channels (point-to-point) 120
Figure 27 – Example of a cabling channel 121
Figure A.1 – Duplex connecting hardware plug 130
Figure A.2 – Duplex connecting hardware adapter 130
Figure A.3 – Duplex patch cord 130
Figure A.4 – Views of crossover patch cords 131
Figure A.5 – Optical fibre sequences and adapter orientation in patch panel for the symmetrical position method 132

Figure A.6 – Optical fibre sequences and adapter orientation in patch panel for the reverse-pair position method 133
Figure A.7 – Array connector cable or patch cord (key-up to key-up) 134
Figure A.8 – Array adapter with aligned keyways 135
Figure A.9 – Transition assembly 136
Figure A.10 – Connectivity method for duplex signals 137
Figure A.11 – Connectivity method for parallel optics channels 138
Figure A.12 – Array connector cable or patch cord (key-up to key-up) 139
Figure A.13 – Array adapter with aligned keyways 139
Figure A.14 – Transition assembly 140
Figure A.15 – Connectivity method for duplex cabling 141
Figure A.16 – Connectivity method for array cabling 142
Figure B.1 – Example of common pathways and spaces in a multi-tenant building 144
Figure B.2 – Example of a campus entrance facility 146
Figure B.3 – Example 1: Common equipment room 148
Figure B.4 – Example 1: Common telecommunications room 149
Figure B.5 – Example 2: Common telecommunications room 149
Figure C.1 – Connection of functional elements providing redundancy 152
Figure F.1 – Connection of functional elements providing redundancy 163
Figure I.1 – Illustration of installation environments 172

Table 1 – Remote powering cabling installation Categories and controls 26
Table 2 – Installed balanced cabling test parameters 33
Table 3 – Minimum sample sizes for alien (exogenous) crosstalk testing 34
Table 4 – Installed optical fibre cabling test parameters 35
Table 5 – Examples of pathway systems 39
Table 6 – Stacking height for non-continuous and interval support pathway systems 45
Table 7 – Design and planning of pathways outside buildings 50
Table 8 – Requirements and recommendations for pathway depths below finished surface 52
Table 9 – Minimum installed clearances above ground for aerial cables 54
Table 10 – Separation recommendations between metallic telecommunications cabling and specific EMI sources 71
Table 11 – Classification of telecommunications cables 73
Table 12 – Minimum separation, S 74
Table 13 – Power cabling factor, P 74
Table 14 – Minimum distance between telecommunications cables and earthed electrodes of power systems in rural and urban environments 81
Table 15 – Minimum distance between telecommunications cables and earthed electrodes of power systems in accordance with ITU-T K.8 81
Table 16 – Minimum clearances and protective measures at crossings between telecommunications cables and various underground services 82
Table 17 – Minimum clearances between aerial telecommunications and overhead power supply cabling 83

Table 18 – Technology-independent channel length vs. temperature 89
Table 19 – Temperature changes for various cable bundle sizes..... 90
Table 20 – Reduction factors for rectangular cable groups..... 91
Table 21 – Level of installation complexity..... 105
Table 22 – Level of operational complexity 106
Table 23 – Minimum requirements of administration systems..... 106
Table 24 – Minimum requirements of operational administration systems..... 108
Table 25 – Labelling requirements 110
Table 26 – Labelling recommendations (additional)..... 111
Table 27 – Infrastructure records for spaces, cabinets, racks, frames and closures 113
Table 28 – Infrastructure records for cables and termination points..... 114
Table 29 – Infrastructure records 115
Table 30 – Infrastructure records for pathways and premises..... 116
Table 31 – Recommendations of installation administration systems..... 118
Table 32 – Recommendations of operational administration systems 118
Table A.1 – Optical fibre colour code scheme used in Annex A..... 129
Table B.1 – Summary of common spaces used to service a multi-tenant building..... 144
Table D.1 – Risk elements in determining a maintenance approach 154
Table E.1 – Minimum requirements for dimensions of primary distribution spaces..... 159
Table E.2 – Requirements for dimensions of secondary distribution spaces 159
Table E.3 – Minimum dimensions of spaces allocated to junction boxes 160
Table E.4 – Recommendations for dimensions of primary distribution spaces 161
Table E.5 – Recommendations for dimensions of secondary distribution spaces..... 161
Table H.1 – Equipment environmental specifications 168
Table I.1 – Temperature changes for remote power installations of Category RP2 170