ISO 18107:2026-02 (E)

Variable refrigerant flow air-to-air conditioners and air-to-air heat pumps - Testing and calculating methods for seasonal performance factors and energy performance mapping approach

Contents

Page

Foreword ..... **v**

1 Scope **1**

2 Normative references **1**

3 Terms and definitions **1**

4 Symbols **14**

5 Cooling mode **19**
5.1 Test 19
5.1.1 General 19
5.1.2 Test requirements 19
5.1.3 Temperature and humidity condition 21
5.1.4 Test conditions 23
5.1.5 Test methods 23
5.1.6 Cooling capacity test results 24
5.2 Calculations 24

6 Heating mode **25**
6.1 Test 25
6.1.1 General 25
6.1.2 Test requirements 25
6.1.3 Temperature conditions 25
6.1.4 Test conditions 28
6.1.5 Test methods 32
6.2 Calculations 33

7 Test methods and uncertainties of measurements **33**
7.1 Test methods 33
7.2 Uncertainty of measurement 33
7.3 Test tolerances 33

8 Test report **34**
8.1 General 34
8.2 Adjustments 34
8.3 Data to be recorded 34

9 Publication of ratings **35**
9.1 Standard ratings 35
9.2 Other ratings 36

10 Energy performance mapping approach for building simulation purposes **36**

Annex A (normative) **Calculations of annual performance factor (APF)** **37**

Annex B (normative) **Calculations of the cooling seasonal performance factor (CSPF) for hot climates** **52**

Annex C (normative) **Calculation of total annual performance factor (TAPF), total cooling seasonal performance factor (TCSPF) and total heating seasonal performance factor (THSPF)** **56**

Annex D (normative) **Integrated energy efficiency ratio (IEER)** **58**

Annex E (normative) **Calculation methods for $E_{ER,d}$, seasonal space cooling efficiency $\eta_{s,c}$, SEER and $S_{EER,on}$** **60**

Annex F (normative) **Calculation method for $C_{OP,d}$, seasonal space heating efficiency $\eta_{s,h}$, SCOP, $S_{COP,on}$ and $S_{COP,net}$ of direct expansion system heat pumps** **67**
Annex G (normative) **Test method for CSPF** **75**
Annex H (normative) **Test method for HSPF** **77**
Annex I (normative) **Refrigerant piping requirements** **78**
Annex J (normative) **Requirements for rating** **79**
Annex K (normative) **Airflow rate setting and measurement** **80**
Annex L (normative) **Test methods for electric power input during thermostat off mode, standby mode, off mode and crankcase heater mode** **83**
Annex M (normative) **Controls verification procedure (CVP) to verify one critical parameter – compressor speed** **85**
Annex N (normative) **Controls verification procedure (CVP) for three critical parameters** **92**
Annex O (informative) **Development of supplemental testing instructions for set-up and testing for three critical parameters CVP** **99**
Annex P (normative) **Capacity test method and requirements for three critical parameters CVP** **105**
Annex Q (informative) **Energy performance mapping approach for air-cooled VRF equipment** **117**
Annex R (informative) **Heat recovery test for air-to-air units with integrated heat recovery** **129**
Annex S (informative) **Recommended compliance criteria for performance testing** **132**
Annex T (informative) **Defrost controls** **133**
Annex U (normative) **Reference outdoor temperature bin distribution for cooling seasonal performance factor (CSPF) calculation for T3 climate** **134**
Annex V (normative) **Applicable climate bins for calculating SEER, $S_{EER,on}$, SCOP, $S_{COP,on}$ and $S_{COP,net}$** **136**
Annex W (informative) **Climate zone classification** **139**
Bibliography **140**