

# DIN EN 12927:2019-08 (E)

## Safety requirements for cableway installations designed to carry persons - Ropes

---

<b>Contents</b>		<b>Page</b>
European foreword .....		5
1	Scope .....	7
2	Normative references .....	7
3	Terms and definitions .....	9
4	Symbols and abbreviated terms .....	12
5	Requirements .....	13
6	Safety principles .....	13
6.1	General .....	13
6.2	Hazard scenarios .....	13
6.3	Safety measures .....	15
7	Selection criteria for ropes and their end fixing .....	16
7.1	Ropes .....	16
7.2	Fibre ropes .....	18
7.2.1	General .....	18
7.2.2	Fibre ropes for carrying-hauling ropes (for ski-tows) .....	18
7.2.3	Fibre ropes for towing cord .....	18
7.3	Rope re-use .....	18
7.4	End fixings (excluding long splice) .....	19
8	Safety factors .....	19
8.1	General .....	19
8.2	Tensile safety .....	19
8.3	Diameter ratio .....	21
8.4	Transverse force ratio .....	22
8.4.1	Roller transverse force ratio .....	22
8.4.2	Carrier transverse force ratio .....	22
9	Discard criteria .....	23
9.1	General .....	23
9.2	Main body of the rope and long splice .....	23
9.2.1	Ropes examined by magnetic rope testing (MRT) .....	23
9.2.2	Ropes examined by visual inspection (VI) .....	23
9.3	Tension ropes .....	24
9.4	Local deterioration .....	24
9.4.1	General .....	24
9.4.2	Main body of the rope .....	24
9.4.3	Splice .....	25
9.5	Rope at end fixing .....	25
9.5.1	Filled socket .....	25
9.5.2	Other end fixing .....	26
10	Storage, handling, transportation and installation (including tensioning, connecting and/ or splicing) .....	26
10.1	General .....	26
10.2	Storage .....	26

10.3	Handling and transportation .....	26
10.4	Installation (including tensioning, connecting and/or splicing) .....	27
10.4.1	General .....	27
10.4.2	Measurements, adjustments and records .....	28
11	Splicing of 6 stranded steel wire ropes .....	28
11.1	General .....	28
11.2	Splice geometry .....	28
11.2.1	General .....	28
11.2.2	Splice dimensions .....	29
11.2.3	Documentation .....	29
12	End fixing .....	29
12.1	General .....	29
12.2	Design .....	29
12.3	Execution and conformity .....	30
12.4	Filled socket .....	30
12.4.1	General .....	30
12.4.2	Design .....	31
12.4.3	Manufacture .....	31
12.4.4	Socketing execution .....	31
12.5	Clamp socket .....	32
12.5.1	General .....	32
12.5.2	Design .....	33
12.5.3	Manufacture .....	33
12.5.4	Execution .....	33
12.6	Drum (Fixing drum and anchor drum) .....	34
12.7	Bolted clamp .....	34
12.7.1	Design .....	34
12.7.2	Manufacture .....	35
12.7.3	Execution and maintenance .....	35
12.8	Wedge socket .....	36
12.8.1	Symmetrical .....	36
12.8.2	Asymmetrical .....	36
12.9	Spliced eye .....	36
12.10	Gripped eye .....	36
12.11	Ferrule secured eye .....	36
12.12	Lever winch .....	36
13	Maintenance .....	36
13.1	General .....	36
13.2	Servicing .....	44
13.2.1	General .....	44
13.2.2	Rope cleaning and lubrication .....	44
13.2.3	Relocation of carrying ropes, fixed grips on monocable aerial ropeways and signal ropes .....	44
13.2.4	Relocation of signal ropes .....	45
13.2.5	End fixing .....	45
13.2.6	Shortening of rope loops .....	45
13.2.7	End fixing of towing cords .....	45
13.3	Inspection .....	45
13.3.1	General .....	45
13.3.2	Personnel requirements .....	46
13.3.3	Initial inspection .....	46
13.3.4	Periodical inspection .....	46
13.3.5	Extraordinary inspection .....	46
13.3.6	Visual inspection (VI) .....	46
13.3.7	Inspection types .....	47
13.3.8	Optical inspection devices (OID) .....	47
13.3.9	Measurements .....	47
13.3.10	Magnetic rope testing .....	49
13.3.11	Radiographic testing .....	49

13.3.12	Report .....	49
13.3.13	Rope indicators .....	49
13.4	Repair .....	50
13.4.1	General .....	50
13.4.2	Stranded rope .....	50
13.4.3	Locked coil rope .....	50
13.4.4	Anchor drum repair .....	51
14	Magnetic rope testing (MRT) .....	51
14.1	General .....	51
14.2	Instrumentation .....	51
14.2.1	Function and operational principles of magnetic flux leakage instruments .....	51
14.2.2	Test head .....	52
14.2.3	Visual display unit and permanent recording instrument .....	52
14.3	Test procedure .....	52
14.3.1	Personnel .....	52
14.3.2	Setting up .....	52
14.3.3	Test execution .....	53
14.3.4	Interpretation of results .....	53
14.3.5	Instrument verification .....	54
15	Fire protection and fire fighting .....	55
Annex A (informative) Guidelines for executing visual inspection type "A" .....		56
Annex B (informative) Magnetic flux density .....		57
Annex C (informative) Magnetic rope testing - Personnel qualifications levels .....		58
Annex D (informative) Bolted clamp - Calculation of slipping force .....		60
Annex E (informative) Determination of intervals related to visual inspections .....		61
E.1	General .....	61
E.2	Operational conditions .....	61
E.2.1	Bendings of stranded ropes .....	61
E.2.2	Number of passages of rollers per year for locked coil ropes .....	61
E.3	Operating personnel .....	62
E.4	Carriers related conditions .....	62
E.5	Cableway configuration .....	63
E.6	Environmental conditions .....	63
E.7	Final evaluation and result .....	63
Annex ZA (informative) Relationship between this European Standard and the Essential Requirements of Regulation (EU) 2016/424 on "Cableway installations" aimed to be covered .....		65