

DIN EN 16704-1:2017-11 (E)

Railway applications - Track - Safety protection on the track during work - Part 1: Railway risks and common principles for protection of fixed and mobile work sites

Contents	Page
European foreword.....	6
1 Scope	7
2 Normative references	7
3 Terms and definitions	8
4 Common principles	17
4.1 General.....	17
4.2 Work done by 3rd party.....	18
5 Principles of risk assessment	18
5.1 General.....	18
5.2 Decision about safety measures	19
5.3 Lines with more than one track	20
5.4 Supervision.....	20
5.5 Documentation.....	20
5.6 Consideration of human behaviour.....	20
5.7 Actualization of risk assessment	21
5.8 Remote controlled equipment of the track.....	21
6 Hierarchy of Safety Measures and parameters for the five railway risks	21
6.1 General.....	21
6.2 Risk 1 – Personnel being struck by a train or injured due to wind drag on open working track (safety of the worker).....	22
6.2.1 General.....	22
6.2.2 Blocking	23
6.2.3 Warning	24
6.3 Risk 2 – Personnel being struck by a train or injured due to wind drag from a train on adjacent track (safety of the worker)	25
6.3.1 General.....	25
6.3.2 Blocking).....	27
6.3.3 Separation.....	28
6.3.4 Warning	29
6.3.5 Additional measures	30
6.3.6 Exceptional circumstances	31
6.4 Risk 3 – Personnel being struck by machine or rail vehicle on blocked track (safety of the worker in the work site)	31
6.4.1 Measures	31
6.4.2 Process on the work site.....	31
6.4.3 Organization.....	32
6.5 Risk 4 – Machines, material or equipment being struck by a train on the adjacent track (safety of the operation/safety of the worker).....	32
6.5.1 General.....	32
6.5.2 Blocking (of the adjacent track).....	33
6.5.3 Separation.....	33
6.5.4 Warning with influence on train circulation).....	34
6.5.5 Additional measures	34

6.6	Risk 5 – Personnel being affected by electric shock/electrocuted (safety of the worker).....	34
6.6.1	General.....	34
6.6.2	Measures for work near fixed electrical equipment.....	34
6.6.3	Disconnection of power.....	36
6.6.4	Induction.....	36
6.6.5	Working procedures.....	36
6.6.6	Traction returning current in rail.....	37
6.6.7	Risk by broken overhead line.....	37
7	Working in tunnels.....	38
7.1	General.....	38
7.2	Safety measures for staff working in tunnels.....	39
8	Designing infrastructure.....	41
8.1	General.....	41
8.2	Designing new infrastructure.....	41
8.3	Designing modifications of the infrastructure.....	41
9	Safety documentation and information.....	42
9.1	General.....	42
9.2	Safety document for planning (safety plan).....	42
9.2.1	General requirements.....	42
9.2.2	Necessary information for the safety document for planning.....	43
9.3	Safety information for briefing.....	44
9.3.1	General.....	44
9.3.2	Content of safety briefing.....	44
9.3.3	Traceability.....	45
9.4	Access to and egress from the work site.....	45
10	Use of personal protective equipment.....	45
	Annex A (normative) Requirements and conditions to manage safety measures.....	46
A.1	Blocking.....	46
A.1.1	Conditions/requirements for blocking:.....	46
A.1.2	Procedure for blocking/de-blocking.....	46
A.1.2.1	Procedure before starting the work.....	46
A.1.2.2	Procedure after completion of the work.....	47
A.2	Separation.....	47
A.2.1	Risk assessment for installation/de-installation of a barrier.....	47
A.2.2	Specific requirements/conditions for using barriers as a separation.....	48
A.2.3	Surveillance of workers (without warning, without barrier).....	48
A.2.4	Visual demarcation line.....	49
A.3	Warning.....	49
A.3.1	Warning process.....	49
A.3.2	Hierarchy in warning systems.....	49
A.3.3	Announcement distance for approaching trains.....	51
A.3.4	Type of signals.....	52
A.3.5	Acoustic planning.....	52

A.3.6 Working with/on (noisy) track working machines:	54
A.3.7 Visual signalling devices	55
A.3.8 Controlling the reaction of workers	55
A.3.9 Specific requirements for LOWS	56
A.3.9.1 General	56
A.3.9.2 Chain of lookouts	56
A.3.9.3 Transmission of the warning by radio	56
A.4 Additional measures	57
Annex B (normative) Parameters in risk assessment	58
Annex C (informative) Matrix of main responsibilities	60
Annex D (informative) Noise levels of machines	65
Annex E (informative) Warning and remembering devices	67
E.1 Collective warning device vs. individual warning device	67
E.2 Combination of acoustic warning and visual signalling devices	67
Annex F (informative) National speed limits for trains approaching work sites	68
Annex G (informative) Functions within the process “warning”	71
Annex H (informative) Model for safety plan on railway risks	73
H.1 General	73
H.2 Safety document for the railway risks 1 to 4	73
H.3 Decision about the safety measures	75
H.3.1 General	75
H.3.2 Decision about the safety measure for the working track (risk 1 and 3)	75
H.3.2.1 Stopping distances machines	75
H.3.2.2 Blocking (hierarchy step 1)	75
H.3.2.3 Warning	76
H.3.3 Decision about the safety measure for the adjacent track (risk 2 and 4)	77
H.3.3.1 Blocking (hierarchy step 1)	77
H.3.3.2 Separation by technical measures	78
H.3.3.3 Warning	78
H.3.3.4 Surveillance of workers without warning	79
H.3.4 Safety measures for access	79
H.3.5 Train circulation, track distance, dangerous zone	79
H.4 Planning of the safety measures	80
H.5 Handing out of the safety document and instructions on the site	82
H.5.1 General	82
H.5.2 Safety supervision	82
H.5.3 Safety execution	82

H.5.4 Contractor / sub-contractor(s)	82
Annex I (informative) Guideline for the decision of blocking the working track in relation to the use of portable equipment.....	84
Annex J (informative) Process and documentation about disconnection of fixed electrical equipment	86
J.1 Process of the decision about disconnection of fixed electrical equipment	86
J.2 Minimum contents for the documentation of the decision about disconnection of fixed electrical equipment.....	86
J.2.1 Information by the contractor	86
J.2.2 Nominated person in control of the electrical equipment.....	87
J.2.3 Documentation of the decision about the disconnection.....	87
J.3 Documentation of disconnection/reconnection of power for work near fixed electrical equipment	88
J.3.1 General.....	88
J.3.2 Instructions for the routing of the document:.....	88
J.3.3 Notice of working cessation	88
Annex K (informative) Examples for the possibility of intruding into the vicinity zone of the fixed electrical equipment.....	90
Annex L (informative) Key aspects of relevant EU Directives	91
L.1 Directive 89/391/EEC	91
L.2 Directive 2004/49/EEC	91
L.3 Directive 92/57/EEC.....	91
Bibliography	92