

# DIN EN 14587-1:2007-09 (E)

## Railway applications - Track - Flash butt welding of rails - Part 1: New R220, R260, R260Mn and R350HT grade rails in a fixed plant

---

| <b>Contents</b>    |  | <b>Page</b> |
|--------------------|--|-------------|
| Foreword .....     |  | 4           |
| Introduction ..... |  | 5           |
| 1                  | Scope .....  | 6           |
| 2                  | Normative references .....                                       | 6           |
| 3                  | Terms and definitions .....                                      | 6           |
| 4                  | Quality management system .....                                  | 7           |
| 5                  | Requirements for the welding process .....                       | 8           |
| 5.1                | General .....  | 8           |
| 5.2                | Clamping force .....   | 8           |
| 5.3                | Pre-heating .....  | 8           |
| 5.4                | Flashing .....   | 8           |
| 5.5                | Upsetting .....  | 8           |
| 5.6                | Upset current .....  | 8           |
| 5.7                | Unclamping .....   | 8           |
| 5.8                | Welding parameters .....   | 8           |
| 5.9                | Steps across the weld .....                                      | 9           |
| 5.10               | Removal of excess upset .....                                    | 10          |
| 5.11               | Post-weld heat treatment .....                                   | 12          |
| 5.12               | Rail end preparation and horizontal alignment requirements ..... | 12          |
| 6                  | Procedure approval .....   | 12          |
| 6.1                | General .....  | 12          |
| 6.2                | Information to be supplied by the purchaser .....                | 12          |
| 6.3                | Sample preparation .....   | 12          |
| 6.4                | Approval tests .....   | 13          |
| 6.4.1              | Visual inspection .....  | 13          |
| 6.4.2              | Weld trimming .....  | 13          |
| 6.4.3              | Weld straightness and flatness .....                             | 13          |
| 6.4.4              | Magnetic particle or dye penetrant inspection .....              | 13          |
| 6.4.5              | Bend testing .....   | 13          |
| 6.4.6              | Macro examination .....  | 13          |
| 6.4.7              | Micro examination .....  | 14          |
| 6.4.8              | Hardness testing .....   | 14          |
| 6.4.9              | Fatigue testing .....  | 15          |
| 6.5                | Test result report .....   | 15          |
| 7                  | Approval of other rail profiles or grades .....                  | 15          |
| 7.1                | General .....  | 15          |
| 7.2                | Sample preparation .....   | 15          |
| 7.3                | Approval tests .....   | 15          |
| 7.4                | Test result report .....   | 15          |
| 8                  | Approval of the Welding Contractor .....                         | 15          |
| 8.1                | General .....  | 15          |
| 8.2                | Welding procedure .....  | 15          |

|   |  |    |
|---|--|----|
| 8.3   | Operators .....  | 15 |
| 8.4   | Supervision .....  | 16 |
| 8.5   | Weld Inspection .....  | 16 |
| 8.6   | Equipment .....  | 16 |
| 9   | Weld production following procedure approval .....   | 16 |
| 9.1   | Weld production .....  | 16 |
| 9.2   | Information to be supplied by the purchaser .....  | 16 |
| 9.3   | Rail end preparation and horizontal rail alignment requirements .....                          | 17 |
| 9.4   | Weld parameter monitoring .....  | 17 |
| 9.5   | Weld identification .....  | 17 |
| 9.6   | Visual inspections .....   | 17 |
| 9.7   | Steps across the weld .....  | 17 |
| 9.8   | Finishing .....  | 17 |
| 9.8.1   | Correction of vertical and horizontal weld alignment .....                                     | 17 |
| 9.8.2   | Profile finishing of the rail head .....   | 17 |
| 9.9   | Weld straightness and flatness .....   | 18 |
| 9.10  | Bend testing .....   | 19 |
| 9.10.1  | General .....  | 19 |
| 9.10.2  | Additional bend test .....   | 19 |
| 9.10.3  | Bend test procedure .....  | 19 |
| 9.10.4  | Interpretation of results .....  | 19 |
| 9.10.5  | Retesting .....  | 20 |
| 9.11  | Documentation .....  | 20 |
| Annex A (normative) Bend test requirements .....                          |  | 21 |
| Annex B (normative) Test weld fracture faces - Recording of defects ..... |  | 23 |
| Annex C (normative) Fatigue test method for flash butt welds .....        |  | 25 |
| C.1   | Scope .....  | 25 |
| C.2   | Test equipment .....   | 25 |
| C.3   | Calibration procedure .....  | 27 |
| C.3.1   | General .....  | 27 |
| C.3.2   | Test piece .....   | 27 |
| C.3.3   | Test piece preparation .....   | 27 |
| C.3.4   | Instrumentation .....  | 27 |
| C.3.5   | Procedure .....  | 27 |
| C.4   | Fatigue test method .....  | 31 |
| C.4.1   | General .....  | 31 |
| C.4.2   | Staircase testing method .....   | 31 |
| C.4.3   | Example of the data analysis of a fatigue strength determination by the staircase method ..... | 33 |
| C.4.4   | Past-the-post testing method .....   | 34 |
| Annex D (normative) Macro examination and micro examination .....         |  | 36 |
| D.1   | Macro examination .....  | 36 |
| D.2   | Micro examination .....  | 36 |
| Annex E (normative) Hardness testing .....                                |  | 37 |
| Bibliography .....  |  | 38 |