

# DIN EN 13434:2022-04 (E)

## Devices to prevent pollution by backflow of potable water - Mechanical disconnecter, flow actuated - Family G, Type B

---

Contents	Page
European foreword .....	4
Introduction.....	5
1 Scope.....	6
2 Normative references.....	6
3 Terms and definitions.....	7
4 Denomination.....	9
5 Designation .....	9
6 Symbolization.....	9
7 Physical-chemical characteristics.....	10
7.1 General.....	10
7.2 Materials .....	10
7.2.1 General.....	10
7.2.2 Dezincification resistant copper alloy .....	10
7.3 Surface of the body .....	10
7.3.1 General.....	10
7.3.2 Epoxy Coating.....	10
7.3.3 Polyamide Powder based Coating .....	10
7.3.4 Other coatings.....	10
8 Design.....	11
8.1 General.....	11
8.2 Relief valve/Obturator.....	11
8.2.1 General requirements.....	11
8.2.2 Mechanical Disconnecter Family G, Type B.....	11
8.3 Disconnection distance.....	12
9 Characteristics and tests .....	12
9.1 General.....	12
9.2 General tolerances .....	12
9.2.1 Tolerance of set parameters.....	12
9.2.2 Accuracy of measuring instruments .....	12
9.3 Expression of the results.....	12
9.4 Dimensional characteristics .....	12
9.4.1 Connections.....	12
9.4.2 Pressure tapping.....	12
9.5 Mechanical characteristics.....	13
9.5.1 General.....	13
9.5.2 Mechanical resistance of the body under pressure.....	13
9.5.3 Endurance.....	14
9.5.4 Torque test of Captive rotating Nuts and Bending Strength – Tightness of the Body	15
9.6 Leak tightness characteristics.....	16
9.6.1 Verification of the leak tightness of the downstream check valve in closing direction.....	16
9.6.2 Verification of the leak tightness of check valve device (opening direction) .....	17

9.6.3	Verification of the leak tightness of the upstream spring loaded obturator in drain position at low pressure (in the opening direction).....	17
9.7	Hydraulic characteristics.....	18
9.7.1	Test rig— General circuit.....	18
9.7.2	Verification of the pressure loss as a function of flow rate .....	19
9.7.3	Verification of the opening and closing pressures of relief valve .....	20
9.7.4	Verification of the relief valve flow rate.....	20
9.8	Compatibility with the products used for shock disinfection of the networks .....	21
9.8.1	Requirement.....	21
9.8.2	Test method .....	21
9.9	Acoustic tests.....	21
9.9.1	General .....	21
9.9.2	Procedure .....	21
10	Order of testing .....	22
11	Marking and technical documents .....	23
11.1	General .....	23
11.2	Marking .....	23
11.3	Technical documents .....	24
12	Presentation at delivery.....	24
Annex A (informative)	Examples of presentation of test results.....	25
Bibliography	.....	28