

# DIN EN 14637:2008-01 (E)

## Building hardware - Electrically controlled hold-open systems for fire/smoke door assemblies - Requirements, test methods, application and maintenance

---

<b>Contents</b>		<b>Page</b>
Foreword .....		5
Introduction .....		6
<b>1</b>	<b>Scope .....</b>	<b>9</b>
<b>2</b>	<b>Normative references .....</b>	<b>9</b>
<b>3</b>	<b>Terms, definitions and abbreviated term .....</b>	<b>11</b>
<b>4</b>	<b>Classification .....</b>	<b>13</b>
4.1	Coding system .....	13
4.2	Category of use (first digit) .....	13
4.3	Durability (second digit) .....	13
4.4	Door type (third digit) .....	13
4.5	Suitability for use on fire/smoke door assemblies (fourth digit) .....	14
4.6	Safety (fifth digit) .....	14
4.7	Corrosion resistance (sixth digit) .....	14
4.8	Example of classification .....	14
<b>5</b>	<b>Requirements and test methods for components of a hold-open system .....</b>	<b>15</b>
5.1	General .....	15
5.2	Fire detectors .....	15
5.2.1	Smoke detectors .....	15
5.2.2	Heat detectors .....	15
5.2.3	Resetting the detectors .....	15
5.3	Power supply units .....	16
5.3.1	All power supply units .....	16
5.3.2	For power supply units with stand-by parallel operation .....	16
5.4	Control units .....	17
5.4.1	General .....	17
5.4.2	Control units in stand-alone hold-open systems (single-line systems) .....	17
5.4.3	Control units in fire detection and fire alarm systems (multi-line systems) .....	17
5.5	Hold-open devices .....	18
5.5.1	General .....	18
5.5.2	Hold-open devices for swing doors .....	18
5.5.3	Hold-open devices for sliding doors, lifting doors, industrial doors and roller shutters .....	18
5.5.4	Automatic door operators .....	19
5.5.5	Low energy/power assisted swing door operators .....	19
5.5.6	Free-swing door closers .....	20
5.6	Auxiliary equipment .....	20
5.6.1	Manual control push-buttons and switches .....	20
5.6.2	Presence sensors (electro-sensitive protective equipment) .....	20
5.6.3	Door position sensors .....	21
5.6.4	Remote indicating devices .....	21
5.6.5	Manual reset .....	21
<b>6</b>	<b>Requirements for the hold-open system .....</b>	<b>21</b>
6.1	Design and performance .....	21
6.2	Product information .....	22
6.2.1	General .....	22

6.2.2	For installation and maintenance .....	22
6.2.3	For initial hold-open system test .....	23
6.3	Requirements not covered under Clause 5 .....	23
6.4	Electromagnetic compatibility (EMC) .....	23
6.5	Additional design requirements for connection of components to fire alarm systems .....	24
6.6	Electrical safety .....	24
6.7	Durability .....	24
6.8	Environmental behaviour .....	25
6.8.1	Dry heat .....	25
6.8.2	Cold .....	25
6.8.3	Damp heat, steady state (operational) .....	25
6.8.4	Corrosion .....	25
6.8.5	Vibration .....	25
6.9	Supply voltage variations .....	25
7	System tests .....	25
7.1	General .....	25
7.2	Test apparatus .....	26
7.3	Theoretical analysis .....	27
7.4	Test methods .....	27
7.4.1	General .....	27
7.4.2	Design verification .....	28
7.4.3	Performance tests .....	28
7.4.4	Check of switching device capabilities of the control unit .....	30
7.4.5	Short-circuit test .....	30
7.4.6	Electrical safety tests .....	30
7.4.7	Electromagnetic compatibility (EMC) tests .....	30
7.4.8	Environmental tests .....	31
7.4.9	Corrosion test .....	32
7.4.10	Vibration test, sinusoidal (operational) .....	33
7.4.11	Vibration test, sinusoidal (endurance) .....	33
8	Marking .....	35
8.1	Components .....	35
8.2	Hold-open system .....	35
A.1	General .....	36
A.2	Restrictions .....	36
A.3	Detectors .....	36
A.3.1	Selection of detector type .....	36
A.3.2	Positioning and number of detectors .....	37
A.4	Selection of hold-open device .....	43
A.4.1	General .....	43
A.4.2	Swing doors .....	43
A.4.3	Sliding doors .....	44
A.4.4	Roller shutter and lifting doors .....	44
A.4.5	Automatic doors .....	44
A.5	Manual release and manual control .....	44
A.5.1	General .....	44
A.5.2	Location of switch/push-button .....	45
A.6	Interconnecting cables .....	45
A.7	Guidance on competence and responsibilities for individual installations in individual buildings .....	45
A.7.1	Planning .....	45
A.7.2	Installation .....	45
E.1	Usage of installations .....	50
E.1.1	General .....	50
E.1.2	Periodic inspection .....	50
Annex C (informative) Recommendations for acceptance inspection of the hold-open system .....		47

<b>Annex B (informative) Recommendations for installation and fixing of the hold-open system .....</b>	<b>46</b>
<b>Annex D (informative) Acceptance inspection report form .....</b>	<b>48</b>
<b>Annex E (informative) Recommendations for usage and maintenance of the hold-open system .....</b>	<b>50</b>
<b>Annex A (informative) Recommendations for planning and design of the hold-open system .....</b>	<b>36</b>
<b>E.2 F.1 General .....</b>	<b>52</b>
<b>F.1.1 Introduction .....</b>	<b>52</b>
<b>F.1.2 Initial type test .....</b>	<b>52</b>
<b>F.1.3 Characteristics .....</b>	<b>52</b>
<b>F.1.4 Use of historical data .....</b>	<b>53</b>
<b>F.1.5 Treatment of calculated values and design .....</b>	<b>53</b>
<b>F.1.6 Sampling, testing and conformity criteria .....</b>	<b>53</b>
<b>F.2 Factory production control (FPC) .....</b>	<b>53</b>
<b>F.2.1 General .....</b>	<b>53</b>
<b>F.2.2 FPC requirements for all manufacturers .....</b>	<b>54</b>
<b>F.3 Further testing of sample systems .....</b>	<b>54</b>
<b>F.3.1 Periodic testing .....</b>	<b>54</b>
<b>F.3.2 Yearly testing .....</b>	<b>54</b>
<b>F.3.3 Manufacturer-specific FPC system requirements .....</b>	<b>54</b>
<b>G.1 Test report .....</b>	<b>57</b>
<b>G.2 List of approved components .....</b>	<b>57</b>
<b>H.1 Introduction .....</b>	<b>58</b>
<b>H.2 Points for analysis .....</b>	<b>58</b>
<b>H.2.1 General .....</b>	<b>58</b>
<b>H.2.2 List of characteristics .....</b>	<b>58</b>
<b>Bibliography .....</b>	<b>62</b>
<b>Figure 1 -- Basic system components with essential functions .....</b>	<b>6</b>
<b>Figure 2 -- Typical system with additional functions and components .....</b>	<b>7</b>
<b>Figure 3 -- Logic diagram for modes of operation of an electrically controlled hold-open system .....</b>	<b>8</b>
<b>Figure A.1 -- Ceiling types and critical dimensions .....</b>	<b>38</b>
<b>Figure A.2 -- Installation area in accordance with A.3.2.1 .....</b>	<b>39</b>
<b>Figure A.3 -- Flow chart to determine the requisite number of detectors .....</b>	<b>40</b>
<b>Figure A.4 -- Typical electrically controlled hold-open system with release of connected hold-open devices triggered directly by the FDAS (see A.3.2.2 a)) .....</b>	<b>41</b>
<b>Figure A.5 -- Typical electrically controlled hold-open system with release of connected hold-open devices by the control unit of the hold-open system driven by the information coming from the FDAS (see A.3.2.2 b)) .....</b>	<b>42</b>
<b>Table G.1 -- List of approved components .....</b>	<b>57</b>
<b>Routine site inspection report form .....</b>	<b>50</b>
<b>Annex G (informative) Type test report and list of approved components .....</b>	<b>57</b>
<b>Annex F (informative) Evaluation of conformity .....</b>	<b>52</b>
<b>Annex H (informative) Example methodology for theoretical analysis .....</b>	<b>58</b>