DIN EN 14199:2012-01 (E)

Execution of special geotechnical works - Micropiles

Contents

Page

Foreword 4

1 Scope 5

2 Normative references 6

3 Terms and definitions 7

4 Information needed for the execution of the works 11
4.1 General 11
4.2 Special features for micropiles: 11
4.3 List of activities 12

5 Geotechnical investigation 12
5.1 General 12
5.2 Specific requirements 13

6 Materials and products 14
6.1 General 14
6.2 Reinforcement and load bearing elements 14
6.2.1 Steel for reinforcement cage elements 14
6.2.2 Steel for load bearing elements 14
6.2.3 Other materials for reinforcement and load bearing elements 14
6.3 Materials for grout, mortar and concrete 14
6.3.1 Cement 14
6.3.2 Aggregates 15
6.3.3 Water 15
6.3.4 Additions and admixtures 15
6.4 Cement grout 15
6.4.8 Quality control 16
6.5 Mortar and Concrete 16
6.5.1 Mortar and concrete in situ 16
6.5.2 Other concrete 17
6.6 Spacers, centralizers and other components 17
6.7 Coatings and corrosion protection compounds 17

7 Considerations related to design 17
7.1 General 17
7.2 Geometrical construction tolerances 18
7.3 Installation 18
7.4 Reinforcement 19
7.5 Connecting elements 19
7.6 Corrosion protection of steel elements 19
7.7 Spacers and centralizers 20
7.8 Micropile enlargement 20
7.9 Connections to the superstructure 21
7.10 Spacing of micropiles 21
7.11 Special requirements for micropiles installed through very weak soils 21
7.12 Micropile shoe 21

8 Execution 21
8.1 General 21

8.2 Site preparation ... 22
8.3 Sequence of installation ... 22
8.4 Drilling ... 22
8.4.1 General ... 22
8.4.2 Use of flushing ... 23
8.4.3 Boreholes supported by casings ... 24
8.4.4 Drilling with continuous flight augers ... 24
8.5 Driving ... 24
8.6 Enlargements ... 24
8.7 Reinforcement and load bearing elements ... 25
8.7.1 Handling and storing ... 25
8.7.2 Joints ... 25
8.7.3 Spacers and centralizers ... 25
8.7.4 Installation ... 25
8.8 Grouting ... 26
8.8.1 General ... 26
8.8.2 Grout preparation ... 26
8.8.3 Borehole testing and pregrouting ... 27
8.8.4 Filling the borehole with grout ... 27
8.8.5 Single step grouting through a temporary casing ... 27
8.8.6 Single step grouting through a load bearing element ... 27
8.8.7 Grouting and filling during driving ... 28
8.8.8 Grouting during drilling ... 28
8.8.9 Multi-stage grouting ... 28
8.9 Concreting ... 28
8.10 Trimming of micropiles ... 28

9 Supervision, testing and monitoring ... 29
9.1 Supervision ... 29
9.2 Monitoring of micropile construction ... 29
9.3 Micropile testing ... 29
9.3.1 General ... 29
9.3.2 Static load tests ... 30
9.3.3 Dynamic load tests and integrity tests ... 31

10 Records ... 31
10.1 General ... 31
10.2 Records for the execution of construction micropiles ... 31
10.3 Records for micropile tests ... 33

11 Special requirements ... 34

Annex A (informative) Execution methods of micropiles ... 40

A.1 Drilled micropiles ... 40
A.2 Displacement micropiles ... 41

Annex B (informative) Guidance on geometrical construction tolerances ... 42

Annex C (informative) Minimum cover (in mm) for reinforcement and bearing element of low strength steel for cast in place micropiles taking into account exposure classes related to environmental actions as defined in EN 206-1 ... 43

Annex D (informative) Guidance on corrosion rates ... 44

Annex E (informative) Borehole testing and pregrouting ... 45

Annex F (informative) Guideline for the preparation of a record for several drilled micropiles ... 46

Annex G (informative) Guideline for the preparation of a record for several driven micropiles ... 47

Bibliography ... 48