

# DIN EN 14199:2015-07 (E)

## Execution of special geotechnical works - Micropiles

---

<b>Contents</b>		<b>Page</b>
Foreword .....		4
<b>1</b>	<b>Scope .....</b>	<b>5</b>
<b>2</b>	<b>Normative references .....</b>	<b>6</b>
<b>3</b>	<b>Terms and definitions .....</b>	<b>7</b>
<b>4</b>	<b>Information needed for the execution of the works .....</b>	<b>11</b>
4.1	General .....	11
4.2	Special features .....	12
4.3	List of activities .....	13
<b>5</b>	<b>Geotechnical investigation .....</b>	<b>13</b>
5.1	General .....	13
5.2	Specific requirements .....	14
<b>6</b>	<b>Materials and products .....</b>	<b>15</b>
6.1	General .....	15
6.2	Reinforcement and load bearing elements .....	15
6.2.1	Steel for reinforcement .....	15
6.2.2	Steel for load bearing elements .....	15
6.2.3	Other materials or grades of steel .....	16
6.3	Materials for grout, mortar and concrete .....	16
6.3.1	Cement .....	16
6.3.2	Aggregates .....	16
6.3.3	Water .....	16
6.3.4	Additions and admixtures .....	16
6.4	Grout .....	16
6.5	Mortar and concrete .....	17
6.6	Spacers, centralisers and other components .....	17
6.7	Coatings and corrosion protection compounds .....	18
<b>7</b>	<b>Considerations related to design .....</b>	<b>18</b>
7.1	General .....	18
7.2	Geometrical construction tolerances .....	19
7.3	Installation .....	19
7.4	Reinforcement and load bearing elements .....	19
7.5	Connecting elements .....	20
7.6	Corrosion protection of steel elements .....	20
7.7	Spacers and centralisers .....	21
7.8	Micropile enlargement .....	21
7.9	Connections to the superstructure .....	22
7.10	Spacing of micropiles .....	22
7.11	Special requirements for micropiles .....	22
<b>8</b>	<b>Execution .....</b>	<b>22</b>
8.1	General .....	22
8.2	Construction tolerances .....	23
8.3	Site preparation .....	23
8.4	Sequence of installation .....	24
8.5	Drilling .....	24

8.5.1	General .....	24
8.5.2	Use of flushing .....	25
8.5.3	Boreholes supported by casings .....	25
8.5.4	Drilling with segmental hollow stem augers .....	25
8.6	Enlargements .....	25
8.7	Reinforcement and load bearing elements .....	26
8.7.1	Handling and storing .....	26
8.7.2	Joints .....	26
8.7.3	Spacers and centralisers .....	27
8.7.4	Installation .....	27
8.8	Filling and grouting .....	27
8.8.1	General .....	27
8.8.2	Grout preparation .....	28
8.8.3	Borehole testing and pregrouting .....	28
8.8.4	Filling the borehole .....	28
8.8.5	Filling or grouting through a temporary casing .....	28
8.8.6	Filling or grouting through a load bearing element .....	29
8.8.7	Grouting during drilling .....	29
8.8.8	Multi-stage grouting .....	29
8.9	Concreting .....	29
8.9.1	Concreting in submerged conditions .....	29
8.9.2	Concreting through a segmental hollow stem augers .....	29
8.9.3	Concreting in dry conditions .....	30
8.10	Trimming of micropiles .....	31
9	Supervision, monitoring and testing .....	32
9.1	Supervision .....	32
9.2	Monitoring of micropile construction .....	32
9.3	Micropile testing .....	33
9.3.1	General .....	33
9.3.2	Static load tests .....	33
9.3.3	Dynamic load tests .....	34
9.3.4	Low strain integrity tests .....	34
10	Records .....	35
10.1	General .....	35
10.2	Records for the execution of construction micropiles .....	35
10.3	Records for micropile tests .....	37
11	Special requirements .....	38
Annex A (informative) Execution methods of micropiles .....		51
Annex B (informative) Guidance on minimum cover (in mm) for bearing element of low strength steel for cast in situ micropiles .....		52
Annex C (informative) Borehole testing and pregrouting .....		53
Annex D (informative) Guideline for a record for micropiles .....		54
Annex E (informative) Degree of obligation of the provisions .....		55
Bibliography .....		62