

DIN EN 14199:2015-07 (E)

Execution of special geotechnical works - Micropiles

| Contents | | Page |
|-----------------|--|-------------|
| Foreword | | 4 |
| 1 | Scope | 5 |
| 2 | Normative references | 6 |
| 3 | Terms and definitions | 7 |
| 4 | Information needed for the execution of the works | 11 |
| 4.1 | General | 11 |
| 4.2 | Special features | 12 |
| 4.3 | List of activities | 13 |
| 5 | Geotechnical investigation | 13 |
| 5.1 | General | 13 |
| 5.2 | Specific requirements | 14 |
| 6 | Materials and products | 15 |
| 6.1 | General | 15 |
| 6.2 | Reinforcement and load bearing elements | 15 |
| 6.2.1 | Steel for reinforcement | 15 |
| 6.2.2 | Steel for load bearing elements | 15 |
| 6.2.3 | Other materials or grades of steel | 16 |
| 6.3 | Materials for grout, mortar and concrete | 16 |
| 6.3.1 | Cement | 16 |
| 6.3.2 | Aggregates | 16 |
| 6.3.3 | Water | 16 |
| 6.3.4 | Additions and admixtures | 16 |
| 6.4 | Grout | 16 |
| 6.5 | Mortar and concrete | 17 |
| 6.6 | Spacers, centralisers and other components | 17 |
| 6.7 | Coatings and corrosion protection compounds | 18 |
| 7 | Considerations related to design | 18 |
| 7.1 | General | 18 |
| 7.2 | Geometrical construction tolerances | 19 |
| 7.3 | Installation | 19 |
| 7.4 | Reinforcement and load bearing elements | 19 |
| 7.5 | Connecting elements | 20 |
| 7.6 | Corrosion protection of steel elements | 20 |
| 7.7 | Spacers and centralisers | 21 |
| 7.8 | Micropile enlargement | 21 |
| 7.9 | Connections to the superstructure | 22 |
| 7.10 | Spacing of micropiles | 22 |
| 7.11 | Special requirements for micropiles | 22 |
| 8 | Execution | 22 |
| 8.1 | General | 22 |
| 8.2 | Construction tolerances | 23 |
| 8.3 | Site preparation | 23 |
| 8.4 | Sequence of installation | 24 |
| 8.5 | Drilling | 24 |

| | | |
|--|--|----|
| 8.5.1 | General | 24 |
| 8.5.2 | Use of flushing | 25 |
| 8.5.3 | Boreholes supported by casings | 25 |
| 8.5.4 | Drilling with segmental hollow stem augers | 25 |
| 8.6 | Enlargements | 25 |
| 8.7 | Reinforcement and load bearing elements | 26 |
| 8.7.1 | Handling and storing | 26 |
| 8.7.2 | Joints | 26 |
| 8.7.3 | Spacers and centralisers | 27 |
| 8.7.4 | Installation | 27 |
| 8.8 | Filling and grouting | 27 |
| 8.8.1 | General | 27 |
| 8.8.2 | Grout preparation | 28 |
| 8.8.3 | Borehole testing and pregrouting | 28 |
| 8.8.4 | Filling the borehole | 28 |
| 8.8.5 | Filling or grouting through a temporary casing | 28 |
| 8.8.6 | Filling or grouting through a load bearing element | 29 |
| 8.8.7 | Grouting during drilling | 29 |
| 8.8.8 | Multi-stage grouting | 29 |
| 8.9 | Concreting | 29 |
| 8.9.1 | Concreting in submerged conditions | 29 |
| 8.9.2 | Concreting through a segmental hollow stem augers | 29 |
| 8.9.3 | Concreting in dry conditions | 30 |
| 8.10 | Trimming of micropiles | 31 |
| 9 | Supervision, monitoring and testing | 32 |
| 9.1 | Supervision | 32 |
| 9.2 | Monitoring of micropile construction | 32 |
| 9.3 | Micropile testing | 33 |
| 9.3.1 | General | 33 |
| 9.3.2 | Static load tests | 33 |
| 9.3.3 | Dynamic load tests | 34 |
| 9.3.4 | Low strain integrity tests | 34 |
| 10 | Records | 35 |
| 10.1 | General | 35 |
| 10.2 | Records for the execution of construction micropiles | 35 |
| 10.3 | Records for micropile tests | 37 |
| 11 | Special requirements | 38 |
| Annex A (informative) Execution methods of micropiles | | 51 |
| Annex B (informative) Guidance on minimum cover (in mm) for bearing element of low strength steel for cast in situ micropiles | | 52 |
| Annex C (informative) Borehole testing and pregrouting | | 53 |
| Annex D (informative) Guideline for a record for micropiles | | 54 |
| Annex E (informative) Degree of obligation of the provisions | | 55 |
| Bibliography | | 62 |