

DIN EN 1536:2015-10 (E)

Execution of special geotechnical work - Bored piles (includes Amendment A1:2015)

Contents		Page
Foreword		4
1	Scope	5
2	Normative references	10
3	Terms and definitions	11
4	Information needed for the execution of the work	16
4.1	General	16
4.2	Special features	17
5	Geotechnical investigation	18
5.1	General	18
5.2	Specific requirements	18
6	Materials and products	19
6.1	Constituents	19
6.1.1	General	19
6.1.2	Bentonite	19
6.1.3	Polymers	20
6.1.4	Cement	20
6.1.5	Aggregates	20
6.1.6	Water	20
6.1.7	Additions	20
6.1.8	Admixtures	20
6.2	Support fluids	20
6.2.1	Bentonite suspensions	20
6.2.2	Polymer solutions	22
6.3	Concrete	22
6.3.1	General	22
6.3.2	Aggregates	23
6.3.3	Cement contents	23
6.3.4	Water/cement ratio	23
6.3.5	Admixtures	23
6.3.6	Fresh concrete	23
6.3.7	Sampling and testing on site	24
6.4	Grout	24
6.5	Reinforcement	25
6.6	Additional inserted products	25
7	Considerations related to design	25
7.1	General	25
7.2	Piles forming a wall	26
7.3	Excavation	27
7.4	Precast concrete elements	27
7.5	Reinforcement	27
7.5.1	General	27
7.5.2	Longitudinal reinforcement	28
7.5.3	Transverse reinforcement	28
7.6	Steel tubes and profile elements	29
7.7	Minimum and nominal cover	29

8	Execution	30
8.1	Construction tolerances	30
8.1.1	Geometrical tolerances	30
8.1.2	Installation tolerances for reinforcement cage	31
8.1.3	Tolerances for trimming	32
8.2	Excavation	32
8.2.1	General	32
8.2.2	Methods and tools	34
8.2.3	Excavations supported by casings	34
8.2.4	Excavations supported by fluids	36
8.2.5	Boring with continuous flight augers	36
8.2.6	Unsupported excavation	37
8.2.7	Enlargements	38
8.3	Reinforcement	38
8.3.1	General	38
8.3.2	Joints	38
8.3.3	Bending of reinforcement	38
8.3.4	Assembly of cages	39
8.3.5	Spacers	39
8.3.6	Installation	40
8.4	Concreting and trimming	40
8.4.1	General	40
8.4.2	Concreting in dry conditions	41
8.4.3	Concreting in submerged conditions	42
8.4.4	Extraction of casings	43
8.4.5	Permanent casings or linings	44
8.4.6	Concreting of continuous flight auger piles	44
8.4.7	Prepacked piles	45
8.4.8	Loss of immersion of tremie pipe or casing	45
8.4.9	Precast concrete elements and steel tubes or profiles	46
8.4.10	External grouting of bored piles	46
8.4.11	Trimming	47
8.5	Pile walls	47
9	Supervision, testing and monitoring	48
9.1	Construction controls	48
9.2	Bored pile testing	49
9.2.1	General	49
9.2.2	Pile load tests	49
9.2.3	Integrity tests	50
10	Records	50
11	Special Requirements	53
	Annex A (informative) Glossary	55
	Annex B (informative) Examples for details and frequencies for monitoring and testing	64
	Annex C (informative) Sample records	69
	Annex D (informative) Obligation of the provisions	76
	Bibliography	82