

DIN EN 1366-10:2017-07 (E)

Fire resistance tests for service installations - Part 10: Smoke control dampers (includes Amendment A1:2017)

Contents	Page
European foreword	5
Introduction	7
1 Scope	8
2 Normative references	8
3 Terms and definitions	8
4 Test equipment	13
4.1 General	13
4.2 Connecting duct for multi compartment fire resisting smoke control damper: maintenance of opening test and EN 1366-2 test	13
4.3 Volume flow measuring station for multi compartment fire resisting smoke control damper: maintenance of opening test and EN 1366-2 test	13
4.4 Plenum for High Operating Temperature (HOT) test	13
4.5 Cycling equipment	13
4.6 Condensing unit	14
4.7 Gas temperature measuring devices	14
4.8 Exhaust fan system	14
4.9 Perforated plate	14
4.10 Flow measurement nozzles (fire test)	15
4.11 Ambient leakage measuring device	15
4.12 Pressure sensors for differential pressure control	15
4.13 Welded connecting tube	15
4.14 Extract fan connecting duct	15
4.15 Extraction fan	16
4.16 Thermocouples	16
4.17 Oxygen measuring equipment	16
4.18 Observation windows	16
5 Test specimen	16
5.1 Cross-section	16
5.2 Design	16
5.2.1 General	16
5.2.2 Supporting constructions	16
5.2.3 Inclusion of grilles	17
6 Test methods	17
6.1 General	17
6.2 Initiation regimes for elevated temperature and fire tests	17
6.2.1 Smoke control damper for systems with automatic activation	17
6.2.2 Smoke control damper for systems with manual intervention:	18
6.3 Cycling test requirements (to form part of the sequences of testing defined below)	18
6.3.1 General	18
6.3.2 Smoke control damper to be used in dedicated Smoke control systems, operated only in the case of emergency	18
6.3.3 Differential pressure conditions	19

6.4	Single compartment smoke control dampers mounted on the surface of a duct	19
6.4.1	Sequence	19
6.4.2	Ambient leakage	19
6.4.3	Cycling test	19
6.4.4	Elevated temperature test	19
6.5	Multi compartment fire resisting smoke control dampers	20
6.5.1	Fire resistance test according to EN 1366-2 (for units mounted within or on the face of a compartment structure)	20
6.5.2	Maintenance of opening test (for units mounted within a compartment structure)	21
6.5.3	Horizontal duct test for surface mounted smoke control dampers on a horizontal duct	21
6.5.4	Vertical duct test for surface mounted smoke control dampers	22
6.6	Multi compartment fire resisting smoke control dampers (HOT Classification)	24
6.6.1	Fire resistance test (for units mounted within or on the face of a compartment structure)	24
6.6.2	High operating test (HOT 400/30 - cycling and maintenance of opening test)	25
7	Test procedure	25
7.1	Pre-test calibration	25
7.1.1	Oxygen-measuring instrument	25
7.1.2	Perforated plate	25
7.1.3	Leakage measurement at ambient temperature	26
7.2	Fire test	26
7.2.1	Extraction fan	26
7.2.2	Ignition of furnace	26
7.2.3	Furnace conditions	26
7.2.4	Temperatures and pressures	27
7.2.5	Oxygen measurements	27
7.2.6	General observations	27
7.2.7	Reduction of cross-section/ maintenance of opening	27
7.2.8	Leakage calculations	27
7.3	Termination of test	27
8	Test report	28
9	Direct field of application of test results	28
9.1	General	28
9.2	Smoke control damper sizes	28
9.3	Pressure difference	29
9.4	Elevated temperatures	29
9.5	Cycling tests	29
9.5.1	Smoke control dampers meeting the cycling requirements for modulating applications ..	29
9.5.2	Smoke control dampers meeting the cycling requirements for use with combined smoke control and general HVAC applications and for smoke control systems that are cycle checked every day	29
9.5.3	Smoke control dampers meeting the cycling requirements for smoke control dampers that are operated only in the case of emergency	29
9.6	Initiation method	29
9.7	Application to duct constructions other than that tested	30
9.7.1	Single compartment smoke control dampers	30
9.7.2	Multi compartment smoke control dampers	30
Annex A (normative)	Cycling test	51
A.1	General	51
A.2	Purpose of the test	51
A.3	Method of Application	51
A.3.1	General	51
A.3.2	Smoke Control Damper with single blade	51
A.3.3	Smoke control damper with multi blades of smaller area	52
A.3.4	Report	53

A.4	Background for the torque value (informative)	53
A.4.1	Threshold rates of the working condition of the system	53
A.4.2	Previous experience	53
Annex B (normative)	Leakage calculation from oxygen measurement	55
B.1	General	55
Annex C (normative)	Maintenance of opening calculation	56
C.1	Calculation of the theoretical total mass M_{max} of hot gases during the fire test	56
C.1.1	Basis	56
C.1.2	Method	56
C.1.3	Summary	57
C.2	Calculation of the actual total mass M_{actual} of hot gases during the fire test	58
C.2.1	Basis	58
C.2.2	Method	59
C.2.3	Summary	59
C.3	Graphical representation of typical integral calculation from data	61
Bibliography		62