ISO/TR 21136:2017-04 (E)

Timber structures - Vibration performance criteria for timber floors

Contents

Page

Foreword iv

Introduction v

1 Scope 1

2 Normative references 1

3 Terms and definitions 1

4 Background 1

5 Mechanism of timber floor vibration response to human normal walking actions 6
5.1 Characteristics of footstep force 6
5.2 Responses of timber floors to the footstep force 7
5.3 Parameters correlated to human acceptability of timber floor vibration 8
5.4 General forms of human acceptability criterion of timber floor vibration 8

6 Comprehensive procedure using a large database 8
6.1 General 8
6.2 Subjective evaluation procedure and questionnaire for laboratory floors 9
6.3 Subjective evaluation procedure and questionnaire for field timber floors 10
6.4 Statistical analysis to derive human acceptability criterion from timber floor vibration database 10
6.5 Verification of the criterion derived using a new database 11

7 Simplified procedure using a small database 11

Annex A (informative) Subjective evaluation questionnaire for laboratory floors used by FPInnovations, Canada 12

Annex B (informative) An example of the application of the comprehensive procedure to establish acceptability criterion for light frame timber floors in Canada 14

Annex C (informative) Example of application of the simplified procedure to establish acceptability criterion (design criterion) for cross laminated timber (CLT) floors in Canada 19

Annex D (informative) EC5 design criteria and calculation methods for criterion parameters 24

Annex E (informative) Hamm et al. design criteria and calculation methods for criterion parameters 26

Bibliography 28