

# DIN EN 16907-6:2019-04 (E)

## Earthworks - Part 6: Land reclamation earthworks using dredged hydraulic fill

---

<b>Contents</b>		<b>Page</b>
European foreword .....		5
Introduction.....		6
1	Scope .....	7
2	Normative references .....	7
3	Terms and definitions.....	9
4	Symbols and abbreviations.....	13
5	Stages of land reclamation projects.....	13
6	Design aspects for earthworks with dredged hydraulic fill.....	14
6.1	Introduction.....	14
6.2	Basis of Design .....	14
6.2.1	General .....	14
6.2.2	Scope of Work .....	15
6.2.3	The project site.....	15
6.2.4	Standards and Codes of Practice .....	15
6.2.5	Functional requirements .....	15
6.2.6	Boundary conditions and constraints.....	15
6.2.7	Performance requirements .....	16
6.2.8	Site data.....	16
6.2.9	Borrow area .....	16
6.2.10	Environmental constraints .....	17
6.2.11	Regulations, permits and licenses .....	17
6.3	General design aspects .....	17
6.3.1	Earth-structure design aspects.....	17
6.3.2	Morphological and environmental aspects.....	17
6.4	Boundary conditions affecting the execution.....	18
6.4.1	General .....	18
6.4.2	Locations of land reclamation area, borrow area and disposal site .....	18
6.4.3	Soil conditions at the land reclamation area.....	18
6.4.4	Soil conditions at the borrow area .....	18
6.4.5	Suitable fill material properties.....	19
6.4.6	Dredging close to existing structures.....	19
6.4.7	Construction tolerances .....	19
6.4.8	Return of process water .....	19
6.4.9	Ground improvement of the fill mass and the subsoil .....	19
6.4.10	Project execution time and milestones .....	19
6.5	Earthworks design considerations .....	20
6.5.1	Introduction.....	20
6.5.2	Land reclamation area.....	20
6.5.3	Borrow area.....	20
6.5.4	Available quantity of suitable fill material.....	21
6.6	Design considerations in relation to dredging equipment.....	22
7	Technical specifications for earthworks with dredged hydraulic fill .....	22
7.1	Introduction.....	22

7.2	Technical specifications for the subsoil .....	22
7.3	Technical specifications for the fill mass .....	22
7.4	Technical specifications for the fill material .....	23
8	Data collection .....	23
8.1	General .....	23
8.2	Bathymetrical and topographical data .....	24
8.3	Geotechnical and geophysical data .....	24
8.3.1	General .....	24
8.3.2	Geotechnical and geophysical data in the borrow area.....	24
8.3.3	Geotechnical and geophysical data in the land reclamation area.....	26
8.4	Hydrological and meteorological data.....	26
8.5	Seismic data .....	27
8.6	Morphological and environmental data.....	27
8.6.1	General .....	27
8.6.2	Sediment transport.....	27
8.6.3	Total Suspended Solids (TSS) and turbidity .....	28
8.6.4	Organic matter and gas.....	28
8.6.5	Contaminants .....	28
8.6.6	Underwater sound.....	28
8.7	Seabed features .....	28
8.8	Site constraints.....	29
9	Equipment.....	30
9.1	Selection of the dredging equipment.....	30
9.1.1	General .....	30
9.1.2	Selection of the dredging equipment based on the capabilities of the equipment .....	30
9.1.3	Selection of the dredging equipment based on hydraulic and meteorological conditions.....	30
9.1.4	Selection of the dredging equipment based on the presence of shipping.....	31
9.1.5	Selection of the dredging equipment based on environmental restrictions .....	31
9.2	Typical dredging equipment .....	31
9.3	Accuracy and tolerances .....	32
9.4	Minimal vessel requirements for monitoring and data logging.....	32
10	Design of the execution of earthworks with dredged hydraulic fill.....	33
10.1	Construction .....	33
10.1.1	General .....	33
10.1.2	Preparation phase.....	33
10.1.3	Construction phase .....	34
10.1.4	Post-construction phase.....	35
10.2	Selection of placement method .....	35
10.3	Preparation of the seabed for dredging and for the land reclamation works.....	37
10.4	Containment bunds.....	38
10.5	Process water management.....	39
10.6	Water table in the land reclamation area.....	39
10.7	Use of cohesive or fine grained materials.....	39
10.8	Ground improvement.....	39
11	Quality control.....	40
11.1	General .....	40
11.2	Quality Control Plan.....	40
11.3	Monitoring and testing .....	41
11.4	Dimensions and boundary conditions .....	41

11.4.1	Borrow area.....	41
11.4.2	Land reclamation area.....	42
11.5	Quality of the fill material.....	42
11.5.1	Source material in borrow area .....	42
11.5.2	Fill material in land reclamation area .....	42
11.6	Fill mass .....	42
11.6.1	Bearing capacity.....	42
11.6.2	Slope stability.....	43
11.6.3	Consolidation and deformations.....	43
11.6.4	<i>In situ</i> density and density index .....	43
11.6.5	Permeability .....	45
11.6.6	Frequency of testing .....	45
11.6.7	Environmental monitoring .....	46
11.7	Handover documentation.....	47
Annex A (informative) Non EN and non ISO test and monitoring methods .....		48
A.1	General .....	48
A.2	Electrical piezometer .....	49
A.3	Inclinometer .....	49
A.4	Rod and plate settlement gauges .....	49
A.5	Settlement profiling tube.....	50
A.6	Trial embankment.....	50
A.7	Zone Loading Test .....	51
Annex B (informative) Determination of minimum and maximum dry densities and density index.....		52
B.1	General .....	52
B.2	British Standard procedures.....	52
B.2.1	General .....	52
B.2.2	Minimum dry density of sands.....	52
B.2.3	Minimum dry density of gravelly soils.....	53
B.2.4	Maximum dry density of sands.....	53
B.2.5	Maximum dry density of gravelly soils .....	53
B.3	ASTM procedures.....	53
B.3.1	General .....	53
B.3.2	Minimum index dry density.....	53
B.3.3	Maximum index dry density .....	54
B.4	Density index.....	54
Bibliography .....		55