DIN EN ISO 22477-6:2026-06 (E)

Geotechnical investigation and testing - Testing of geotechnical structures - Part 6: Load testing of soil nails and rock bolts (ISO 22477-6:2026)

Contents

Page

Foreword ... **iv**

1 Scope ... **1**

2 Normative references ... **1**

3 Terms, definitions and symbols ... **2**
3.1 Terms, definitions ... 2
3.2 Symbols ... 3

4 Equipment ... **3**
4.1 Test set-up ... 3
4.2 Reaction system ... 4
4.3 Loading device ... 4
4.4 Load measurement ... 5
4.5 Displacement measurement ... 5
4.6 Time and temperature measurement ... 5

5 Test elements ... **5**
5.1 General ... 5
5.2 Sacrificial elements ... 6
5.3 Production elements ... 6

6 Execution of the test ... **6**
6.1 Time period between installation of test element and testing ... 6
6.2 Test preparation ... 6
6.3 Proof load ... 6
6.4 Datum load ... 7
6.5 Check of the de-bonded length ... 7

7 Test report ... **7**
7.1 General ... 7
7.2 Data report ... 7
7.3 Interpretative report ... 8

8 Test Method A ... **8**
8.1 General ... 8
8.2 Investigation test ... 8
8.2.1 Loading procedure ... 8
8.2.2 Measurement and checks ... 9
8.2.3 Interpretation of data ... 9
8.3 Suitability test ... 11
8.3.1 Loading procedure ... 11
8.3.2 Measurement and checks ... 12
8.3.3 Interpretation of data ... 12
8.4 Acceptance test ... 13
8.4.1 Loading procedure ... 13
8.4.2 Measurement and checks ... 14
8.4.3 Interpretation of data ... 14

9 Test Method B ... **14**
9.1 General ... 14
9.2 Loading procedure ... 15
9.3 Measurement and checks ... 17
9.4 Interpretation of data ... 17

Annex A (informative) **Creep rate α and critical creep load P_c** ... **18**

Bibliography ... **19**