

ISO 16904:2016-02 (E)

Petroleum and natural gas industries - Design and testing of LNG marine transfer arms for conventional onshore terminals

Contents		Page
Foreword		vi
1 Scope	1	1
2 Normative references		1
3 Terms and definitions		2
4 Abbreviated terms		9
5 Design of the arms		10
5.1 Definition of the length and the configuration of the arms, arms description		10
5.1.1 General		10
5.1.2 Balancing		10
5.1.3 Arms dimensions and clearances		11
5.2 Design basis		11
5.2.1 Product line diameter and product data		11
5.2.2 Material and grades		11
5.2.3 Stress analysis		12
5.3 Swivel joints		15
5.3.1 General		15
5.3.2 Product sealing arrangement		16
5.3.3 Bearing system		16
5.3.4 External sealing arrangement		16
5.3.5 Design		16
5.4 Structural bearings		17
5.4.1 Design		17
5.4.2 Protection of structural bearings		18
5.4.3 Grease sampling point		18
5.5 Accessories		18
5.5.1 Adjustable support (jack)		18
5.5.2 Nitrogen injection line		18
5.5.3 Stowing locking device		18
5.5.4 Ladders and platforms		19
5.5.5 Vapour recovery lines		19
5.5.6 Liquid nitrogen line		19
5.5.7 Thermal insulation		19
5.5.8 Ice fall protection		19
5.6 Pipework and fitting		19
5.6.1 Process connections		19
5.6.2 Drain connection		19
5.6.3 Plugged connection		20
5.6.4 Valve		20
5.6.5 Connection flange		20
5.6.6 Gasket		20
5.7 Welding		20
5.8 Corrosion protection and embrittlement protection		20
5.8.1 Corrosion protection		20
5.8.2 Embrittlement protection		20
5.9 Maintenance		21

6	Safety systems	21
6.1	General	21
6.2	Two stage alarm and shutdown system	22
6.2.1	First stage	22
6.2.2	Second stage	22
6.3	Monitoring and alarm systems	22
6.3.1	Alarm envelopes	22
6.3.2	Arm positioning alarms system	22
6.3.3	Arm constant position monitoring system (CPMS)	23
6.3.4	Pressure and hydraulic level alarm	23
6.4	ERS	23
6.4.1	General	23
6.4.2	Design of ERS	23
6.4.3	Safety devices on ERS	24
6.5	Safety devices	24
6.5.1	Fire safety requirements	24
6.5.2	Electrical safety requirements	25
6.5.3	Failure of electrical power supply	25
6.5.4	Stray current protectors	26
6.5.5	Bonding	26
7	Connection with the ship	26
7.1	General	26
7.2	Design of QCDC	26
7.3	QCDC system	27
7.4	Flange cover	27
8	Hydraulic and electric control systems	28
8.1	General	28
8.2	Arms operations	28
8.3	Hydraulic components	29
8.4	Electric components	30
8.5	Testing of control systems	30
8.6	Remote control	30
8.7	Transfer arms jetty control console	30
9	Inspection and tests	31
9.1	General	31
9.2	Prototype test	31
9.2.1	General	31
9.2.2	Swivel joint	31
9.2.3	ERS	34
9.2.4	QCDC	35
9.3	Manufacturing inspection and tests	37
9.3.1	General	37
9.3.2	Materials	37
9.3.3	Welding	37
9.3.4	Non-destructive test	37
9.3.5	Dimensional inspection	37
9.3.6	Pressure test	37
9.3.7	ERS	38
9.3.8	QCDC	38
9.3.9	Insulating flange (stray current protector)	39
9.3.10	Hydraulic circuit test	39
9.4	Factory acceptance tests	39
9.5	Site acceptance tests	40
9.5.1	General	40
9.5.2	Transfer arm assembly	41
9.5.3	Hydraulic circuit	42
10	Quality assurance and control	42

10.1	Quality system	42
10.2	Quality plan	42
11	Required documentation	43
	Annex A (informative) Design data sheets	44
	Annex B (informative) Referencetableandfigures	58
	Annex C (informative) Documentation requirements	62
	Bibliography	67