DIN EN ISO 20257-1:2020-12 (E)

Installation and equipment for liquefied natural gas - Design of floating LNG installations - Part 1: General requirements (ISO 20257-1:2020, Corrected version 2020-10)

Contents

Page

European foreword ... **7**

Foreword ... **8**

Introduction ... **9**

1 Scope ... **10**

2 Normative references ... **10**

3 Terms, definitions and abbreviated terms ... **12**
3.1 Terms and definitions ... 12
3.2 Abbreviated terms ... 17

4 Basis of design ... **20**
4.1 Site and meteocean conditions ... 20
4.1.1 Site study ... 20
4.1.2 Earthquake ... 22
4.1.3 Location ... 22
4.1.4 Other studies ... 23
4.2 Design criteria ... 23
4.2.1 General ... 23
4.2.2 Topsides ... 24
4.2.3 Transfer systems ... 25
4.2.4 Hull ... 29
4.2.5 LNG storage ... 31
4.2.6 Mooring ... 32
4.2.7 Pipe-work ... 34

5 Health, safety and the environment ... **35**
5.1 General ... 35
5.1.1 Main objectives ... 35
5.1.2 Main principles ... 36
5.2 Identification of safety and environmental barriers and design requirements ... 36
5.2.1 General ... 36
5.2.2 Purpose ... 37
5.2.3 Safety and environmental barriers ... 37
5.2.4 Generic barriers ... 38
5.2.5 Safety and environmental barriers identification process ... 38
5.2.6 Safety and environmental barriers design requirements ... 39
5.2.7 Safety and environmental barriers design requirements certification ... 40
5.3 Environmental considerations ... 40
5.3.1 General ... 40
5.3.2 Floating LNG installations specificities ... 40
5.3.3 Environmental aspects identification ... 41
5.3.4 Environmental design review ... 41
5.3.5 Environmental design requirements ... 41
5.4 Safety considerations ... 48
5.4.1 General ... 48
5.4.2 Safety strategies and philosophies ... 49
5.4.3 Safety reviews ... 49
5.4.4 Qualitative risk assessment, QRA and specific safety studies ... 52
5.4.5 Risk prevention measures (typical list) ... 56
5.4.6 Emergency response ... 69

5.5 Occupational health and industrial hygiene considerations 71
5.5.1 Occupational health and industrial hygiene aspects identification 71
5.5.2 Chemical exposure 71
5.5.3 Biological factor 72
5.5.4 Legionella 73
5.5.5 Thermal stress 73
5.5.6 Hot/cold surfaces 74
5.5.7 Support functions to operators - Project with permanent operators on-board or in the facility 74
5.5.8 Lighting 74
5.5.9 Water availability and quality intended for human consumption 75
5.5.10 Noise and vibration 75
5.6 Ergonomics and human factor 77
6 Mooring and stationkeeping 77
6.1 General 77
6.2 Permanent stationkeeping in open waters 78
6.2.1 Stationkeeping concepts 78
6.2.2 Design requirements 79
6.3 Permanent stationkeeping in nearshore or docked conditions 79
6.3.1 Stationkeeping concepts 79
6.3.2 Design requirements 80
6.3.3 Emergency departure of floating LNG installation 81
6.4 Mooring systems for special project design conditions 81
6.4.1 Disconnectable mooring 81
6.4.2 Permanent mooring for a limited project life 82
6.5 Short-duration mooring of a visiting LNGC for loading/unloading 82
6.5.1 General 82
6.5.2 Ship-to-ship mooring in open waters 83
6.5.3 Mooring in docked or nearshore conditions 83
6.5.4 Mooring to an SPM terminal 83
6.5.5 Design requirements 83
6.6 Infrastucture design for jetty moorings 84
6.6.1 General 84
6.6.2 Jetty elevation 84
6.6.3 Corrosion protection of the marine infrastructure 84
6.6.4 LNG spillage containment 85
6.6.5 Power supply from/to jetty to the FSRU/FLNG 85
6.6.6 Navigation aids 85
6.6.7 Emergency response and evacuation route 85
6.7 Transfer of material and personnel 85
7 Hull design 86
7.1 Hull structural design 86
7.1.1 Design philosophy 86
7.1.2 Design methods 86
7.1.3 Codes and standards 86
7.1.4 Limit states for floating structures 87
7.1.5 Design situations for ULS 87
7.1.6 Design situations for SLS 87
7.1.7 Design situations for FLS 88
7.1.8 Design situations for ALS 88
7.1.9 Site-specific design 88
7.1.10 Cargo containment loads 89
7.1.11 Fatigue 89
7.1.12 Slamming 89
7.1.13 Green water 89

7.1.14 Topsides and external loads 90
7.1.15 Accidental loads 90
7.2 Stability and watertight integrity 90
7.2.1 General 90
7.2.2 Stability 90
7.2.3 Watertight and weathertight integrity 91

8 LNG storage 91
8.1 General 91
8.2 Sloshing loads 92
8.2.1 Intermediate filling levels: Operating conditions of FSRU/FLNG 92
8.2.2 Intermediate filling levels: Operating conditions of cargo transfers (STS) 93
8.3 Boil-off gas management 93
8.4 Rollover prevention management 93
8.4.1 Background 93
8.4.2 Detection and prevention 94
8.5 Vent systems for LNG storage 94
8.5.1 General 94
8.5.2 Pressure relief systems 94
8.5.3 Vacuum relief systems 95

9 LNG transfer system 96
9.1 Functional requirements 96
9.2 Design of transfer systems 97
9.2.1 Operating envelope 97
9.2.2 Transfer system design 98

10 Boil-off gas handling and recovery 100
10.1 General 100
10.2 BOG collection system 100
10.3 System of gas return to LNGC or to FLNG facility 101
10.4 Boil-off gas recovery 101
10.5 Gas compressor 101
10.6 Flare/vent 101

11 Low temperature pipework 101
11.1 General 101
11.2 Piping components 102
11.2.1 General 102
11.3 Pipe 102
11.3.1 General 102
11.3.2 Pipe joints 102
11.3.3 Pipe supports 103
11.3.4 Compensation of contractions due to cold 103
11.3.5 Differential displacement between offshore structures 103
11.4 Valves 103
11.4.1 Relief valves 104
11.5 Thermal insulation 104
11.5.1 General 104
11.5.2 Piping insulation 105
11.5.3 Fire behaviour 105
11.5.4 Gas absorption 105
11.5.5 Moisture resistance 105
11.5.6 Differential movements 106
11.5.7 Thickness determination 106
11.6 Prevention of zinc contamination of austenitic steel 106

12 Utilities systems 106
12.1 Classification of systems 106
12.1.1 Essential services 106
12.1.2 Emergency services 107
12.2 Electrical 107
12.2.1 Design and engineering principles 107
12.2.2 Electrical system design 108
12.2.3 Design and selection of equipment and cables 111
12.3 Instrument air system 112
12.4 Hydraulic systems 112

13 Process and safety control and monitoring systems 112
13.1 General description 112
13.2 Process control system 113
13.2.1 Principle 113
13.2.2 Process control system design 113
13.3 Marine control system 113
13.4 Interfaces floating LNG installation/onshore 113
13.5 Safety control system (safety instrumented and F&G control systems) 114
13.5.1 Principle 114
13.5.2 ESD and safety actions 114
13.5.3 System capabilities 115
13.6 Closed circuit TV 115
13.7 Metering 115
13.7.1 Background 115
13.7.2 Cargo metering 116
13.8 Communications 116
13.9 Environmental monitoring and control 116

14 Security management 117
14.1 General 117
14.2 Offshore access 117
14.3 Onshore access 117

15 Commissioning 118
15.1 General 118
15.2 Systemization and schedule 118
15.3 Implementation 118
15.4 Safety 119
15.5 Organization 120
15.6 Handover 120
15.7 Start-up and performance test 120

16 Inspection and maintenance 120
16.1 General 120
16.2 Specific requirements for floating LNG installations 121
16.2.1 Cargo tank 121
16.2.2 Mooring 121
16.2.3 Process piping systems 121
16.2.4 Transfer systems 121

17 Preservation and corrosion protection 121
17.1 Specific requirements for non-seagoing vessels 121
17.2 Painting and coating 121
17.3 Cathodic protection 122
17.4 Impact of use of seawater as heating medium and active fire protection 122

18 Preparation for operations **122**
19 Specific requirements for conversion of existing installations to floating LNG installations **122**
Annex A (informative) **Risk-based analysis** **124**
Annex B (informative) **Safety studies** **128**
Annex C (normative) **Definition of reference flow rates for LNG boil-off calculations** **135**
Annex D (normative) **Design basis and criteria of an LNG transfer system** **139**
Annex E (informative) **Seismic classification** **151**
Annex F (informative) **Assessment of novel technology** **154**
Annex G (informative) **Environmental, occupational health and industrial hygiene aspects** **157**
Bibliography **162**