DIN EN 1474-2:2024-07 (E)

Installation and equipment for liquefied natural gas - Design and testing of marine transfer systems - Part 2: Design and testing of transfer hoses (includes Corrigendum :2023)

Contents

Page

European foreword 4

1 Scope 5

2 Normative references 5

3 Terms, definitions and abbreviations 5
3.1 Terms and Definitions 5
3.2 Abbreviations 10

4 Applications and Qualification Categories 10
4.1 Applications 10
4.2 Qualification Categories 10

5 Description of typical LNG transfer hose assembly designs and accessories 11
5.1 General 11
5.2 Mandatory components 11
5.3 Optional components 12
5.4 Typical construction of LNG transfer hose assemblies 12
5.4.1 Main hose categories 12
5.4.2 Corrugated metal hose assemblies 13
5.4.3 Thermoplastic multi-layer (non-vulcanized) hose assemblies (Composite hose assemblies) 15
5.4.4 Hose-in-hose with annular space 16

6 Design features of the LNG transfer hoses assemblies 17
6.1 General 17
6.2 Transfer Hose Assembly technology design parameters 17
6.3 Project Specific Design Parameters 18
6.3.1 Selection of hose assembly length 18
6.3.2 Service life 18
6.3.3 Selection of buoyancy and submersion 18
6.3.4 Selection of insulation 18
6.3.5 Selection of external protection 19
6.3.6 Selection of leak detection 19
6.4 Component details - End fitting 19
6.4.1 General 19
6.4.2 Termination 20
6.4.3 Connector 20
6.4.4 Bending stiffener/restrictor (optional) 20
6.5 Hose assembly handling / lifting device 20
6.6 Safety systems 20
6.6.1 Leak detection (optional) 20
6.6.2 Fire safety requirements 21
6.6.3 Electrical safety requirements 21
6.7 Connection to the ship 21
6.8 Hydraulic and electric control systems 21

7 Qualification Requirements 21

7.1 Foreword 21
7.2 Qualification process 22
7.2.1 General Principle 22
7.2.2 Qualification Levels Specific Requirements 22
7.2.3 Certification range definition from a tested hose assembly 24
7.2.4 Certification extension and update 25
7.3 Hose Assembly tests 25
7.3.1 General 25
7.3.2 Hose assembly property characterization tests 26
7.3.3 Qualification tests with acceptance criteria 34

8 Quality assurance and control 44
8.1 General 44
8.2 Material selection 44
8.3 Manufacturing 45
8.3.1 Manufacturing basics 45
8.3.2 Traceability 45
8.3.3 Marking 45
8.3.4 Packing and Preservation 46
8.4 Factory acceptance tests 46
8.4.1 General 46
8.4.2 Tests to be performed on every hose assembly 46

9 Documentation 46
9.1 Purchasing Guidelines 46
9.2 Design, Qualification and Manufacturing Documentation 46
9.3 As-built documentation/Manufacturing Data Book 47
9.4 Operation manual 47

Annex A (informative) Purchasing guidelines table 49

Annex B (informative) Guidelines for additional testing program 52

Annex C (Informative) Guidelines for Hose Qualification Categories (HQCs) Selection 59

Annex D (informative) Surge pressure considerations for LNG hose assemblies 61

Annex E (Informative) Pressure Leak Tests - justification about maximum allowed permeability rate and leak detection value 62

Bibliography 64