

ISO 21573-2:2020 (E)

Building construction machinery and equipment — Concrete pumps — Part 2: Procedure for examination of technical parameters

Contents

	Foreword
1	Scope
2	Normative references
3	Terms and definitions
4	Test items of performances
5	Overall parameters
5.1	Operating mass
5.1.1	Measuring conditions
5.1.2	Measuring apparatus and accuracy requirement
5.1.3	Measuring procedure
5.1.3.1	Measuring method
5.1.3.2	Calculation method
5.2	Overall dimensions
5.2.1	Conditions for taking measurements
5.2.2	Measuring apparatus and accuracy requirement
5.2.3	Measuring procedure
5.2.3.1	General
5.2.3.2	Overall length
5.2.3.3	Overall width
5.2.3.4	Overall height
5.2.3.5	Wheelbase
6	Pumping performance
6.1	Piston pump
6.1.1	Pumping output
6.1.1.1	General
6.1.1.2	Measuring conditions
6.1.1.3	Measuring apparatus and accuracy requirement
6.1.1.4	Measuring preparations
6.1.1.5	Measuring procedure
6.1.1.5.1	Measuring method
6.1.1.5.2	Calculation method
6.1.2	Concrete delivery pressure
6.1.2.1	Measuring conditions
6.1.2.2	Measurement equipment and accuracy requirement
6.1.2.3	Measuring preparations
6.1.2.4	Measuring procedure
6.2	Rotary pump
6.2.1	Single-roller rotary pump (see A.1)
6.2.1.1	Pumping output
6.2.1.2	Delivery pressure
6.2.2	Double-roller rotary pump (see A.2)
6.2.2.1	Pumping output
6.2.2.2	Delivery pressure
7	Feeding height of hopper
7.1	Measuring conditions
7.2	Measurement equipment and accuracy requirement

- 7.3 Measuring procedure
- 8 Performance of water pump
 - 8.1 Measuring conditions
 - 8.2 Measurement equipment and accuracy requirement
 - 8.3 Measuring procedure
 - 8.3.1 Relief pressure of water system
 - 8.3.2 Water output without load
- 9 Performance of concrete-placing boom
 - 9.1 Measuring conditions
 - 9.2 Measurement equipment and accuracy requirement
 - 9.3 Measuring procedure
 - 9.3.1 Maximum length of the concrete-placing boom
 - 9.3.1.1 Measuring method
 - 9.3.1.2 Calculation method
 - 9.3.2 Maximum height of the concrete-placing boom
 - 9.3.2.1 Measuring method
 - 9.3.2.2 Calculation method
 - 9.3.3 Concrete-placing boom section folding angle
 - 9.3.4 Length of concrete-placing boom section
 - 9.3.5 Concrete-placing boom operation zone
 - 9.3.6 Minimum unfolding/folding time and average speed of concrete-placing boom section
 - 9.3.7 Maximum slewing speed
 - 9.3.7.1 Measuring method
 - 9.3.7.2 Calculation method
 - 9.3.8 Maximum slewing angle
 - 9.3.9 Concrete-placing boom system pressure
- 10 Performance of outriggers
 - 10.1 Span of outrigger
 - 10.1.1 Measuring conditions
 - 10.1.2 Measurement equipment and accuracy requirement
 - 10.1.3 Measuring procedure
 - 10.1.3.1 General
 - 10.1.3.2 Front and rear outrigger span
 - 10.1.3.3 Left and right outrigger span
 - 10.2 Maximum load on each outrigger
 - 10.2.1 Measuring conditions
 - 10.2.2 Measuring apparatus and accuracy requirement
 - 10.2.3 Measuring procedure
 - 10.3 Speed of outriggers movement
 - 10.3.1 Measuring conditions
 - 10.3.2 Measuring apparatus and accuracy requirement
 - 10.3.3 Measuring procedure
 - 10.3.3.1 Swing speed of outriggers
 - 10.3.3.1.1 Measuring method
 - 10.3.3.1.2 Calculation method
 - 10.3.3.2 Horizontal telescoping speed of outriggers
 - 10.3.3.2.1 Measuring method
 - 10.3.3.2.2 Calculation method
 - 10.3.3.3 Speed of vertical outrigger cylinder
 - 10.3.3.3.1 Measuring method
 - 10.3.3.3.2 Calculation method
 - 10.4 Outriggers system pressure
 - 10.4.1 Measuring conditions
 - 10.4.2 Measuring apparatus and accuracy requirement
 - 10.4.3 Measuring procedure
- Annex A (informative) Theoretic pumping output and delivery pressure of rotary pump
 - A.1 Single-roller rotary pump
 - A.2 Double -roller rotary pump