

DIN EN ISO 11298-3:2018-12 (E)

Plastics piping systems for renovation of underground water supply networks - Part 3: Lining with close-fit pipes (ISO 11298- 3:2018)

Contents		Page
European foreword		4
Foreword		5
Introduction		6
1	Scope	8
2	Normative references	8
3	Terms and definitions	9
3.1	General.....	9
3.2	Techniques.....	9
3.3	Characteristics.....	10
3.4	Materials.....	10
3.5	Product stages.....	10
3.6	Service conditions.....	10
3.7	Joints.....	11
4	Symbols and abbreviated terms	11
4.1	Symbols.....	11
4.2	Abbreviated terms.....	12
5	Pipes at the “M” stage	12
5.1	Materials.....	12
5.1.1	Virgin material.....	12
5.1.2	Reprocessable and recyclable material.....	12
5.2	General characteristics.....	12
5.2.1	Appearance.....	12
5.2.2	Colour.....	12
5.3	Material characteristics.....	13
5.4	Geometric characteristics.....	13
5.5	Mechanical characteristics.....	13
5.6	Physical characteristics.....	13
5.7	Jointing.....	13
5.8	Marking.....	13
5.9	Regional requirements for pipes.....	14
6	Fittings at the “M” stage	14
6.1	Requirements.....	14
6.2	Marking.....	14
6.3	Regional requirements for fittings.....	14
7	Ancillary components	14
8	Fitness for purpose of the installed lining system at the “I” stage	14
8.1	Materials.....	14
8.2	General characteristics.....	14
8.3	Material characteristics.....	14
8.4	Geometric characteristics.....	15
8.5	Mechanical characteristics.....	15
8.6	Physical characteristics.....	16
8.7	Additional characteristics.....	16
8.8	Sampling.....	16
8.9	Regional requirements for the installed lining system.....	16

9	Installation practice	16
9.1	Preparatory work.....	16
9.2	Storage, handling and transport of pipes and fittings.....	17
9.3	Equipment.....	17
9.3.1	Butt fusion and debanding equipment.....	17
9.3.2	Reduction equipment.....	17
9.3.3	Pipe skids/rollers.....	18
9.3.4	Winching and rod-pulling equipment.....	18
9.3.5	Pipe entry guides.....	18
9.3.6	Reforming equipment.....	18
9.3.7	Electrofusion equipment.....	18
9.3.8	Inspection equipment.....	18
9.3.9	Lifting equipment.....	19
9.4	Installation.....	19
9.5	Process-related inspection and testing.....	19
9.6	Lining termination.....	20
9.7	Reconnection to the existing pipeline system.....	20
9.8	Final inspection and testing.....	20
9.9	Documentation.....	20
	Annex A (normative) Factory-folded heat-reverted polyethylene (PE) pipe —	
	Determination of memory ability	21
	Bibliography	23