

# DIN EN 17522:2025-03 (E)

## Design and construction of backfilled and grouted borehole heat exchangers

---

<b>Contents</b>		<b>Page</b>
	European foreword .....	6
1	Scope .....	7
2	Normative references .....	7
3	Terms and definitions .....	8
4	Geological and environmental aspects .....	10
4.1	General .....	10
4.2	Geological and hydrogeological risks .....	11
4.2.1	Artesian aquifers .....	11
4.2.2	Stacked aquifers with different groundwater potential .....	11
4.2.3	Groundwater and soil chemistry .....	11
4.2.4	Gas occurrence .....	11
4.2.5	Ground stability .....	11
4.2.6	Contrasting geological sequence (Alternated bedding) .....	12
4.2.7	Karst geology .....	12
4.2.8	Frost susceptibility .....	13
4.2.9	Groundwater protection area .....	13
4.3	Anthropogenic risks and constraints .....	13
4.4	Environmental aspects .....	13
4.4.1	General .....	13
4.4.2	Influence on groundwater .....	13
4.4.3	Environmental impact due to construction works .....	14
5	System description .....	15
5.1	General .....	15
5.2	Borehole heat exchanger .....	15
5.3	Horizontal piping .....	17
5.4	Manifolds .....	17
5.5	Thermal plant .....	18
6	Materials .....	18
6.1	General properties .....	18
6.2	Materials .....	18
6.2.1	Polymeric materials .....	18
6.2.2	Connection methods .....	20
6.2.3	Metallic materials .....	21
6.3	Heat transfer fluid .....	21
6.4	Backfilling materials .....	22
6.4.1	General .....	22
6.4.2	Grouting material .....	22
6.4.3	Other backfilling materials requirements .....	23
6.5	Component selection criteria .....	23
6.5.1	General .....	23
6.5.2	BHE loops .....	23
6.5.3	Horizontal pipes .....	24
6.5.4	Manifolds .....	24
6.5.5	Heat transfer fluid .....	24
7	Design .....	24

7.1	Steps of design .....	24
7.2	Sizing .....	25
7.2.1	General .....	25
7.2.2	General methodology .....	26
7.2.3	Thermal properties of the ground .....	29
7.2.4	Thermal Response Test (TRT) .....	30
7.2.5	Calculation and modelling procedure .....	37
7.2.6	Simulation .....	38
7.2.7	Hydraulic design .....	39
8	Construction .....	40
8.1	General .....	40
8.2	Site preparation and planning .....	40
8.3	Drilling .....	41
8.3.1	General .....	41
8.3.2	Drilling diameter .....	41
8.3.3	Drilling fluid .....	41
8.3.4	Monitoring and documentation of the drilling process .....	41
8.4	Borehole heat exchanger loop .....	42
8.5	Borehole heat exchanger loop installation .....	42
8.6	Backfilling and grouting procedure .....	43
8.6.1	General .....	43
8.6.2	Grouting procedure .....	43
8.6.3	Other backfilling procedure .....	44
8.7	Horizontal piping .....	44
8.8	Testing and checking of BHE - Leakage, flow, grouting, geophysical measurements .....	45
8.9	Manifolds .....	45
9	Start-up .....	46
9.1	General .....	46
9.2	Heat transfer fluid .....	46
9.3	Filling of the system .....	46
9.4	Drying of new buildings .....	46
9.5	Commissioning .....	46
9.6	Documentation .....	47
10	Operation, monitoring and maintenance .....	47
10.1	Operation .....	47
10.2	Monitoring .....	47
10.2.1	General .....	47
10.2.2	Temperature .....	48
10.2.3	Pressure .....	48
10.2.4	Flow rate .....	48
10.3	Maintenance .....	48
11	Renovation .....	49
12	Decommissioning .....	49
12.1	General .....	49
12.2	Heat transfer fluid .....	49
12.3	Borehole heat exchangers .....	49
12.3.1	Backfilled boreholes .....	49
12.4	Horizontal pipes .....	50
12.5	Documentation .....	50
	Annex A (informative) Insulation of horizontal piping .....	51
	Annex B (informative) Example simulation time .....	52
B.1	General .....	52
B.2	Single house, unbalanced energy design .....	52
B.3	Field of 30 houses with an unbalanced design .....	53

<b>B.4</b>	<b>Field with 400 houses with an unbalanced design .....</b>	<b>54</b>
<b>B.5</b>	<b>Conclusion .....</b>	<b>54</b>
	<b>Annex C (informative) Commissioning checklist .....</b>	<b>55</b>
	<b>Annex D (informative) Examples of thermal conductivity and volumetric - heat capacity of the underground .....</b>	<b>57</b>
	<b>Annex E (informative) Main drilling methods .....</b>	<b>59</b>
	<b>Bibliography .....</b>	<b>61</b>