DIN EN 17522:2025-03 (E)

Design and construction of backfilled and grouted borehole heat exchangers

Contents

Page

European foreword 6

1 Scope 7

2 Normative references 7

3 Terms and definitions 8

4 Geological and environmental aspects 10
4.1 General 10
4.2 Geological and hydrogeological risks 11
4.2.1 Artesian aquifers 11
4.2.2 Stacked aquifers with different groundwater potential 11
4.2.3 Groundwater and soil chemistry 11
4.2.4 Gas occurrence 11
4.2.5 Ground stability 11
4.2.6 Contrasting geological sequence (Alternated bedding) 12
4.2.7 Karst geology 12
4.2.8 Frost susceptibility 13
4.2.9 Groundwater protection area 13
4.3 Anthropogenic risks and constraints 13
4.4 Environmental aspects 13
4.4.1 General 13
4.4.2 Influence on groundwater 13
4.4.3 Environmental impact due to construction works 14

5 System description 15
5.1 General 15
5.2 Borehole heat exchanger 15
5.3 Horizontal piping 17
5.4 Manifolds 17
5.5 Thermal plant 18

6 Materials 18
6.1 General properties 18
6.2 Materials 18
6.2.1 Polymeric materials 18
6.2.2 Connection methods 20
6.2.3 Metallic materials 21
6.3 Heat transfer fluid 21
6.4 Backfilling materials 22
6.4.1 General 22
6.4.2 Grouting material 22
6.4.3 Other backfilling materials requirements 23
6.5 Component selection criteria 23
6.5.1 General 23
6.5.2 BHE loops 23
6.5.3 Horizontal pipes 24
6.5.4 Manifolds 24
6.5.5 Heat transfer fluid 24

7 Design 24

7.1 Steps of design ... 24
7.2 Sizing ... 25
7.2.1 General ... 25
7.2.2 General methodology ... 26
7.2.3 Thermal properties of the ground ... 29
7.2.4 Thermal Response Test (TRT) ... 30
7.2.5 Calculation and modelling procedure ... 37
7.2.6 Simulation ... 38
7.2.7 Hydraulic design ... 39

8 Construction ... 40
8.1 General ... 40
8.2 Site preparation and planning ... 40
8.3 Drilling ... 41
8.3.1 General ... 41
8.3.2 Drilling diameter ... 41
8.3.3 Drilling fluid ... 41
8.3.4 Monitoring and documentation of the drilling process ... 41
8.4 Borehole heat exchanger loop ... 42
8.5 Borehole heat exchanger loop installation ... 42
8.6 Backfilling and grouting procedure ... 43
8.6.1 General ... 43
8.6.2 Grouting procedure ... 43
8.6.3 Other backfilling procedure ... 44
8.7 Horizontal piping ... 44
8.8 Testing and checking of BHE - Leakage, flow, grouting, geophysical measurements ... 45
8.9 Manifolds ... 45

9 Start-up ... 46
9.1 General ... 46
9.2 Heat transfer fluid ... 46
9.3 Filling of the system ... 46
9.4 Drying of new buildings ... 46
9.5 Commissioning ... 46
9.6 Documentation ... 47

10 Operation, monitoring and maintenance ... 47
10.1 Operation ... 47
10.2 Monitoring ... 47
10.2.1 General ... 47
10.2.2 Temperature ... 48
10.2.3 Pressure ... 48
10.2.4 Flow rate ... 48
10.3 Maintenance ... 48

11 Renovation ... 49

12 Decommissioning ... 49
12.1 General ... 49
12.2 Heat transfer fluid ... 49
12.3 Borehole heat exchangers ... 49
12.3.1 Backfilled boreholes ... 49
12.4 Horizontal pipes ... 50
12.5 Documentation ... 50

Annex A (informative) Insulation of horizontal piping ... 51

Annex B (informative) Example simulation time ... 52

B.1 General ... 52
B.2 Single house, unbalanced energy design ... 52
B.3 Field of 30 houses with an unbalanced design ... 53

B.4 Field with 400 houses with an unbalanced design 54
B.5 Conclusion 54

Annex C (informative) Commissioning checklist 55

Annex D (informative) Examples of thermal conductivity and volumetric - heat capacity of the underground 57

Annex E (informative) Main drilling methods 59

Bibliography 61