

DIN EN 17522:2025-03 (E)

Design and construction of backfilled and grouted borehole heat exchangers

Contents		Page
	European foreword	6
1	Scope	7
2	Normative references	7
3	Terms and definitions	8
4	Geological and environmental aspects	10
4.1	General	10
4.2	Geological and hydrogeological risks	11
4.2.1	Artesian aquifers	11
4.2.2	Stacked aquifers with different groundwater potential	11
4.2.3	Groundwater and soil chemistry	11
4.2.4	Gas occurrence	11
4.2.5	Ground stability	11
4.2.6	Contrasting geological sequence (Alternated bedding)	12
4.2.7	Karst geology	12
4.2.8	Frost susceptibility	13
4.2.9	Groundwater protection area	13
4.3	Anthropogenic risks and constraints	13
4.4	Environmental aspects	13
4.4.1	General	13
4.4.2	Influence on groundwater	13
4.4.3	Environmental impact due to construction works	14
5	System description	15
5.1	General	15
5.2	Borehole heat exchanger	15
5.3	Horizontal piping	17
5.4	Manifolds	17
5.5	Thermal plant	18
6	Materials	18
6.1	General properties	18
6.2	Materials	18
6.2.1	Polymeric materials	18
6.2.2	Connection methods	20
6.2.3	Metallic materials	21
6.3	Heat transfer fluid	21
6.4	Backfilling materials	22
6.4.1	General	22
6.4.2	Grouting material	22
6.4.3	Other backfilling materials requirements	23
6.5	Component selection criteria	23
6.5.1	General	23
6.5.2	BHE loops	23
6.5.3	Horizontal pipes	24
6.5.4	Manifolds	24
6.5.5	Heat transfer fluid	24
7	Design	24

7.1	Steps of design	24
7.2	Sizing	25
7.2.1	General	25
7.2.2	General methodology	26
7.2.3	Thermal properties of the ground	29
7.2.4	Thermal Response Test (TRT)	30
7.2.5	Calculation and modelling procedure	37
7.2.6	Simulation	38
7.2.7	Hydraulic design	39
8	Construction	40
8.1	General	40
8.2	Site preparation and planning	40
8.3	Drilling	41
8.3.1	General	41
8.3.2	Drilling diameter	41
8.3.3	Drilling fluid	41
8.3.4	Monitoring and documentation of the drilling process	41
8.4	Borehole heat exchanger loop	42
8.5	Borehole heat exchanger loop installation	42
8.6	Backfilling and grouting procedure	43
8.6.1	General	43
8.6.2	Grouting procedure	43
8.6.3	Other backfilling procedure	44
8.7	Horizontal piping	44
8.8	Testing and checking of BHE - Leakage, flow, grouting, geophysical measurements	45
8.9	Manifolds	45
9	Start-up	46
9.1	General	46
9.2	Heat transfer fluid	46
9.3	Filling of the system	46
9.4	Drying of new buildings	46
9.5	Commissioning	46
9.6	Documentation	47
10	Operation, monitoring and maintenance	47
10.1	Operation	47
10.2	Monitoring	47
10.2.1	General	47
10.2.2	Temperature	48
10.2.3	Pressure	48
10.2.4	Flow rate	48
10.3	Maintenance	48
11	Renovation	49
12	Decommissioning	49
12.1	General	49
12.2	Heat transfer fluid	49
12.3	Borehole heat exchangers	49
12.3.1	Backfilled boreholes	49
12.4	Horizontal pipes	50
12.5	Documentation	50
	Annex A (informative) Insulation of horizontal piping	51
	Annex B (informative) Example simulation time	52
B.1	General	52
B.2	Single house, unbalanced energy design	52
B.3	Field of 30 houses with an unbalanced design	53

B.4 Field with 400 houses with an unbalanced design54
B.5 Conclusion 54
Annex C (informative) Commissioning checklist 55
**Annex D (informative) Examples of thermal conductivity and volumetric - heat capacity of the
underground57**
Annex E (informative) Main drilling methods 59
Bibliography61