

DIN EN 13477-2:2021-12 (E)

Non-destructive testing - Acoustic emission testing - Equipment characterisation - Part 2: Verification of operating characteristics

Contents		Page
European foreword		4
1	Scope	5
2	Normative references	5
3	Terms and definitions	5
4	Required test equipment and test signals	8
4.1	List of required equipment	8
4.2	Test signal waveforms	9
4.2.1	Continuous sine wave	9
4.2.2	Triangular-modulated sine wave burst signal	10
4.2.3	Sin ² -modulated sine wave burst signal	12
4.2.4	Rectangular-modulated sine wave burst signal	13
4.2.5	Rectangular pulse	14
4.2.6	Repetitive signals	14
4.2.7	DC signal	15
4.2.8	Summary of test signals	15
4.3	Test block	15
4.4	Shielding test plate	15
5	Sensor verification	15
5.1	General	15
5.2	Intended purpose	16
5.3	Preparation of the report form and preliminary examination	16
5.4	Sensitivity verification	17
5.4.1	General	17
5.4.2	Test procedure	17
5.5	Verification of the electrical shield crosstalk	18
5.5.1	General	18
5.5.2	Procedure	22
5.6	Pre-amplifier verification of sensor-internal pre-amplifier	22
6	Pre-amplifier verification	23
6.1	Preparation of the report form and preliminary examination	23
6.2	Verification of DC consumption	24
6.2.1	General	24
6.2.2	Verifying a limit or a deviation	25
6.2.3	Procedure	25
6.3	Verification of the pre-amplifier characteristics	26
6.3.1	General	26
6.3.2	Gain verification	26
6.3.3	Bandwidth verification	28
6.3.4	Electronic noise verification	30
6.3.5	Dynamic range verification	32
6.3.6	Common mode rejection verification	35
6.3.7	Pulsing test	35
7	Acoustic emission signal processor verification	35
7.1	General	35

7.1.1	Overview	35
7.1.2	Preparation of the report form	38
7.2	Signal processor noise verification	39
7.2.1	General	39
7.2.2	Test procedure	40
7.3	Verification of RMS measurement and floating threshold functionality	41
7.3.1	General	41
7.3.2	Test procedure	43
7.4	Verification of the fixed detection threshold	43
7.4.1	General	43
7.4.2	Procedure for signal stimulation and data acquisition	45
7.4.3	Procedure for the data verification	45
7.5	Bandwidth and filter roll-off verification	45
7.5.1	General	45
7.5.2	Data needed for verification of bandwidth and roll-off verification	46
7.5.3	Procedure for signal stimulation and storage	46
7.5.4	Test procedure for bandwidth verification based on stored AE data	46
7.6	Burst signal parameter verification	47
7.6.1	General	47
7.6.2	Maximum amplitude verification	47
7.6.3	Duration verification	50
7.6.4	Rise-time verification	52
7.6.5	Ring-down count verification	54
7.6.6	Energy and signal strength verification	55
8	Verification of the system performance	58
8.1	External parametric input verification	58
8.1.1	General	58
8.1.2	Formulae for parametric input verification	59
8.1.3	Avoiding the use of a high-accuracy digital voltmeter (HADVM)	60
8.1.4	Report form preparation	60
8.1.5	Test procedure for signal stimulation and measurement for parametric input verification	61
8.1.6	Test procedure for parametric input data verification	62
8.2	Pulser verification	62
8.3	System acquisition rate verification	62
8.4	Delta t (t) measurement verification	63
8.5	Software verification	63
9	Test report	64
Annex A (informative) Report form for the sensor performance verification		65
Annex B (informative) Report form for the pre-amplifier performance verification		67
Annex C (informative) Report form for the acoustic emission signal processor verification		70
Annex D (informative) Report form for the external parametric input verification		75
Annex E (informative) List of designations		77
Bibliography		79