

ISO 6963:2024-05 (E)

Bunker cargo loading from oil terminal to bunker tanker using Coriolis mass flow meter

Contents		Page
Foreword		v
Introduction		vi
1	Scope	1
2	Normative references	1
3	Terms and definitions	1
4	Application	6
5	Metrological requirements	7
5.1	General	7
5.2	Mass flow meter requirements	7
5.3	MFM measuring system requirements	8
5.4	Post approval maintenance	9
5.4.1	Meter zero verification frequency	9
5.4.2	Zero verification procedure	9
5.4.3	Meter and ancillary devices verification and/or calibration frequency	9
5.4.4	Software upgrade or update	9
6	System integrity requirements	9
6.1	General	9
6.2	Metrological control	9
6.2.1	Documentation	9
6.2.2	Type approval and pattern evaluation	10
6.3	Security features	10
6.3.1	Equipment security	10
6.3.2	Software security	10
6.3.3	Data security	10
6.3.4	Critical alarm	10
6.4	Installation and commissioning	10
6.4.1	Pre-installation and MFM bunker system sealing plan	10
6.4.2	Installation and re-installation	11
6.4.3	Commissioning	11
6.5	Operational security	11
6.6	Maintenance control	11
6.6.1	Maintenance control of MFM bunker system	11
6.6.2	Re-commissioning	11
7	Meter selection and installation requirements	11
7.1	General	11
7.2	Site survey at terminals	12
7.3	Meter selection	12
7.4	Meter installation	12
7.5	Meter commissioning	13
8	Site acceptance test requirements	13
9	Metering procedures	13

9.1	General	13
9.2	Documentation	13
9.2.1	General	13
9.2.2	System documentation	14
9.2.3	Pre-loading documentation	14
9.2.4	Post-loading documentation	14
9.3	Additional documentation at the terminal	14
9.3.1	Meter totalizer log	14
9.3.2	System documents at the terminal	15
9.4	Pre-loading procedures	15
9.4.1	Pre-loading conference	15
9.4.2	System integrity seals document	15
9.4.3	Meter reading record	15
9.5	Loading procedures	15
9.5.1	General	15
9.5.2	Start of loading	16
9.5.3	End of loading	17
9.6	Post-loading procedures	17
9.6.1	Meter reading record	17
9.6.2	Bunker cargo metering ticket	17
9.6.3	Determination of loaded quantity	17
9.7	Others	18
9.7.1	MFM measuring system failure	18
9.7.2	Disputes	18
10	Bunker cargo quality	18
10.1	Bunker cargo specifications	18
10.2	Sampling	19
10.2.1	Location of sampling equipment	19
10.2.2	Sampling procedure	19
10.3	Documentation	19
Annex A (informative) Uncertainty budget table		20
Annex B (normative) Zero verification procedure		21
Annex C (normative) Metrological and system integrity requirements		22
Annex D (informative) Typical schematic diagram for MFM bunker system (for bunker cargo loading)		23
Annex E (informative) Example of letter of protest for bunker cargo loading		24
Annex F (informative) Bunker cargo claims procedure for quantity dispute		25
Annex G (informative) Example of a bunker cargo sample label		26
Annex H (informative) Example of a certificate of quality		27
Bibliography		28