

# E DIN EN ISO 19901-7:2024-11 (E)

Erscheinungsdatum: 2024-10-04

**Oil and gas industries including lower carbon energy - Specific requirements for offshore structures - Part 7: Station-keeping systems for floating offshore structures and mobile offshore units (ISO/DIS 19901-7:2024); English version prEN ISO 19901-7:2024**

---

<b>Contents</b>	<b>Page</b>
Foreword.....	vi
Introduction.....	vii
<b>1 Scope.....</b>	<b>1</b>
<b>2 Normative references.....</b>	<b>2</b>
<b>3 Terms, Definitions, Symbols, and Abbreviations.....</b>	<b>3</b>
3.1 Terms and Definitions.....	3
3.2 Symbols.....	11
3.3 Abbreviations.....	12
<b>4 Mooring hardware.....</b>	<b>13</b>
4.1 General.....	13
4.2 Off-vessel mooring line components.....	14
4.2.1 Anchors.....	14
4.2.2 Chain.....	14
4.2.3 Fibre rope.....	14
4.2.4 Steel wire rope.....	15
4.2.5 Connecting hardware.....	15
4.2.6 Buoys.....	15
4.2.7 Clump weights.....	15
4.2.8 Mooring Connectors.....	16
4.2.9 Quick release connectors.....	16
4.2.10 Disconnectable turret buoy.....	16
4.3 On-vessel mooring line components.....	16
4.3.1 Fairleads.....	16
4.3.2 Bending shoes.....	16
4.3.3 Chain stoppers.....	16
4.3.4 Uni-joints.....	17
4.3.5 Turret.....	17
4.4 On-vessel tensioning equipment.....	17
4.5 Monitoring equipment.....	17
4.5.1 General.....	17
4.5.2 Line tension / Line Payout.....	18
4.5.3 Floating structure position and heading.....	18
<b>5 Metocean and other site data.....</b>	<b>18</b>
5.1 General.....	18
5.2 Metocean data.....	18
5.2.1 Wave data.....	18
5.2.2 Wind data.....	19
5.2.3 Current data.....	19
5.3 Bathymetry.....	19
5.4 Geotechnical and Geophysical data.....	19
5.5 Marine growth.....	20
5.6 Physicochemical parameters.....	20
5.7 Ice-related.....	20

<b>6</b>	<b>Design and site assessment of station-keeping systems</b>	<b>20</b>
6.1	Fundamental Requirements	20
6.2	Functional requirements	20
6.3	Safety requirements	21
6.4	Planning requirements	22
	6.4.1 General	22
	6.4.2 Design basis	22
	6.4.3 Design Practices	22
	6.4.4 Installation Considerations at Design Stage	23
	6.4.5 Integrity Management strategy	23
6.5	Rules and regulations	23
6.6	Independent verification for permanent systems	24
6.7	Numerical tools	24
6.8	Design conditions	24
	6.8.1 Limit States	24
	6.8.2 Analysis Cases for Ultimate Limit State	25
	6.8.3 Analysis Cases for Serviceability Limit State	27
	6.8.4 Analysis Cases for Fatigue Limit State	28
	6.8.5 Analysis Cases for Accidental Limit State	29
	6.8.6 Analysis Cases for Temporary Phases	29
<b>7</b>	<b>Design and site assessment criteria</b>	<b>30</b>
7.1	Safety factors for mooring component strength	30
	7.1.1 Line tensions	30
	7.1.2 Anchor factors of safety	31
	7.1.3 Factors of safety for buoyancy elements	33
7.2	Vessel offsets and heading	34
7.3	Requirements for clearances	34
	7.3.1 Mooring line with seabed (thrash zone)	34
	7.3.2 Mooring line with sea surface	35
	7.3.3 Mooring line with hull	35
	7.3.4 Mooring line with riser, umbilical, mooring line, pipeline, seabed assets, and exclusion zones	35
	7.3.5 Submerged turret buoy	35
	7.3.6 Anchor with mooring line, pipeline, seabed assets, and exclusion zones	35
7.4	Safety factors for mooring component fatigue resistance	36
<b>8</b>	<b>Analysis</b>	<b>38</b>
8.1	General	38
8.2	Analysis methods	39
8.3	Coupling effects	39
8.4	Environmental loads on the floating structure	40
	8.4.1 Wave forces	40
	8.4.2 Wind forces	40
	8.4.3 Current forces and VIM	41
8.5	Environmental loads on mooring lines and risers	41
	8.5.1 Wave forces	41
	8.5.2 Current forces	41
8.6	Mooring analysis for strength, offsets, and clearances	41
	8.6.1 Basic considerations	41
	8.6.2 Extreme value statistics	41
	8.6.3 Design values for responses to transient wind squalls	42
	8.6.4 Mitigating mooring line trenching effects	42
8.7	Mooring analysis for fatigue	42
	8.7.1 Basic considerations	42
	8.7.2 Analysis Approach	42
	8.7.3 Fatigue damage calculation methods	43
8.8	Response based analysis	45

<b>9</b>	<b>Dynamic positioning and thruster-assisted mooring</b> .....	<b>45</b>
9.1	General.....	45
9.1.1	Dynamic positioning (DP).....	46
9.1.2	Thruster assisted mooring (TAM).....	46
9.2	Equipment.....	46
9.2.1	DP and TAM equipment.....	46
9.2.2	DP equipment classes.....	47
9.3	Available effective thrust.....	47
9.4	Determination of allowable thrust.....	47
9.5	Load sharing of TAM System.....	48
9.5.1	General.....	48
9.5.2	Mean load reduction method.....	48
9.5.3	Weathervaning Units.....	48
9.5.4	System dynamic analysis.....	49
9.6	Failure mode and effects analysis.....	49
9.7	Design, test and maintenance.....	49
9.8	Operating personnel.....	49
9.9	Determination of station-keeping capability.....	50
<b>10</b>	<b>Installation, test load and as-installed survey</b> .....	<b>50</b>
10.1	General.....	50
10.2	Installation considerations and storm-safe criteria.....	50
10.3	Mooring line handling and installation procedure.....	50
10.4	Test loading requirements.....	51
10.4.1	Anchor test load for permanent mooring.....	51
10.4.2	Anchor test load for mobile mooring.....	51
10.5	Installation Tolerances.....	52
10.6	Traceability Records.....	52
10.7	As-installed survey and establishment of as-installed capacity.....	52
<b>11</b>	<b>Integrity Management, Survey &amp; Inspection, and Monitoring</b> .....	<b>53</b>
11.1	Integrity management.....	53
11.2	Surveys & Inspections.....	54
11.3	Mobile moorings.....	55
11.4	Permanent moorings.....	55
11.4.1	Annual surveys.....	55
11.4.2	Complete surveys.....	55
11.5	Evaluation & acceptance/discard criteria.....	56
11.6	Monitoring.....	56
	<b>Annex A (informative) Mooring systems</b> .....	<b>58</b>
	<b>Annex B (informative) Regional information</b> .....	<b>146</b>
	<b>Bibliography</b> .....	<b>192</b>