ISO/TR 12748:2015-10 (E)

Natural Gas - Wet gas flow measurement in natural gas operations

Contents

Page

Foreword vi

Introduction vii

1 Scope 1

2 Terms and Definitions 1

3 Symbols 10

4 Objectives of wet gas flow measurement 13
4.1 Common production scenarios 14
4.2 Production allocation 15
4.3 Flow assurance aspects 16
4.4 WGFM considerations 16
4.5 Reliability in remote WGFM installations 16

5 Flow regimes 17
5.1 Horizontal wet gas flow regimes 17
5.1.1 Stratified flow 18
5.1.2 Slug flow 18
5.1.3 Annular mist flow 18
5.2 Vertical up wet gas flow regimes 18
5.2.1 Churn flow 18
5.2.2 Annular mist flow 19
5.3 Vertical down wet gas flow regimes 19
5.4 Inclined flow 19
5.5 Examples of wet gas flow regimes 19
5.6 Flow regime maps 20
5.7 Different wet gas flow parameters 21
5.8 Water in wet gas flow 21

6 Wet gas flow metering principles 22
6.1 General 22
6.2 In-Line wet gas flow meters 23
6.2.1 Single-phase gas flow meter with correction factor 23
6.2.2 Two-phase wet gas flow meter 24
6.2.3 Multiphase wet gas flow meter 24
6.3 Single-phase gas differential pressure meters with wet gas flow 24
6.3.1 DP Meter design influence on wet gas over-reading 25
6.3.2 Lockhart-Martinelli parameter influence on DP meter wet gas flow over-reading 25
6.3.3 Gas to liquid density ratio influence on DP meter wet gas flow over-reading 25
6.3.4 Gas densiometric Froude number influence on DP meter wet gas flow over-reading 26
6.3.5 DP meter orientation influence on DP meter wet gas flow over-reading 26
6.3.6 Influence of on DP meter wet gas flow over-reading 28
6.3.7 Fluid property influence on DP meter wet gas flow over-reading 28
6.3.8 Meter size/diameter influence on DP meter wet gas flow over-reading 28
6.3.9 Applying DP meter wet gas flow correlations 28
6.4 General discussion on DP meter wet gas correlations 29
6.4.1 Wet gas flow performance characterization vs. published wet gas correlations 29
6.4.2 Horizontally-installed orifice plate meter 29
6.4.3 Horizontally-installed Venturi meter 31

6.4.4 Horizontally-installed cone meter 32
6.5 Generic two-phase wet gas meter designs 33
6.5.1 Multiple single-phase meters in series 33
6.5.2 Differential pressure meter classical DP/permanent pressure loss wet gas meters 35

6.5.3 Fast response sensor system 36
6.6 Multiphase wet gas flow meters 37
6.6.1 Trace water metering with multiphase wet gas flow meters 38
6.6.2 Multiphase wet gas flow meter subsystems 38
6.6.3 Phase fraction device choices 39
6.6.4 Gas volume fraction vs. gas void fraction measurement 41
6.6.5 Semi-empirical multiphase flow calculation -- Slip model 41
6.6.6 PVT (pressure volume temperature) models 42
6.6.7 Multiphase wet gas flow meter required fluid property inputs 42
6.6.8 Multiphase wet gas flow meter phase fraction measurement 42
6.6.9 Measurement of water salinity 43
6.6.10 Multiphase wet gas flow meter redundant subsystems and diagnostics 43
6.6.11 Selection of multiphase wet gas flow meter technologies 44
6.7 Wet gas flow meter performance testing 44
6.8 Virtual metering system (VMS) 45

7 DP Meter Wet Gas Correlation Practical Issues 45
7.1 DP meter wet gas flow installation issues 46
7.1.1 Liquid flow rate estimation techniques 46
7.1.2 Monitoring wet gas liquid loading with a DP meter downstream port 47

8 Design and Installation Considerations 49
8.1 Design considerations 49
8.1.1 Meter orientation and fluid flow 49
8.1.2 Meter location relative to other piping components 50
8.1.3 Use of two-phase flow rate and composition maps 50
8.1.4 Fluid sampling 52
8.1.5 Redundancy and external environmental considerations 52
8.1.6 Security 53
8.1.7 Cost and project schedule implications 54
8.2 Performance specifications 54
8.3 Wet gas flow measurement uncertainty 55
8.3.1 Uncertainty evaluation methodologies 55
8.3.2 Additional factors affecting wet gas flow measurement uncertainty 55
8.3.3 Expressing uncertainty of wet gas flow rates 56

9 Testing, Verification and Calibration 56
9.1 Meter orientation 56
9.2 Comments on flow regimes and mixers 57
9.3 Installation requirements 57
9.4 Wet gas flow characterization tests -- Single-phase DP meter baselines 57
9.5 Wet gas flow facility operational considerations 58
9.5.1 Test facility operational issues -- Achieving thermodynamic equilibrium 58
9.5.2 Test facility operational issues -- Phase flow rate stability 60
9.5.3 Test facility operational issues -- Witnessing of tests 61
9.6 Meter testing in a wet gas flow facility 62

10 Operational and Field Verification Issues 65
10.1 Laboratory reference vs. field hydrocarbon flow composition estimates 66
10.2 Laboratory reference vs. field calibration of phase fractions 66
10.3 Comparisons of multiphase wet gas flow meter and single-phase meter requirements 66
10.3.1 The challenge of supplying multiphase wet gas flow fluid properties 66
10.3.2 Confidential slip models 67
10.4 The importance of correct fluid property predictions 67
10.4.1 The importance of gas properties when metering small liquid flow rates 70
10.4.2 Preparation for fluid property variations during meter service 71
10.4.3 Fluid property sensitivity investigation 71

10.5 The benefit of an initial wet gas flow facility test 73
10.6 Line size limitations for some multiphase meters 73
10.7 In situ wet gas flow meter verification 73
10.7.1 Reconciliation factors and meter output confidence 74
10.8 Operation and maintenance 74
10.8.1 System redundancy and diagnostics 74
10.8.2 Operating WGFM diagnostics 75
10.9 Miscellaneous operational issues 76
10.9.1 Wet gas flow and DP transmitters 76
10.9.2 Software and fluid property update procedures 77
10.9.3 Long term trending comparisons with test facility/factory characterization 77

11 Common Field Issues 77
11.1 Inefficient separator systems 77
11.2 Separator systems -- An adverse environment for single-phase meters 78
11.2.1 Separator Outlet deployment 79
11.2.2 Gas Measurement at the separator outlet 79
11.2.3 Liquid Turbine Meter 80
11.2.4 Practical limitations of wet gas flow metering with separator technology 80
11.3 Wet gas flow meter practical problems 81
11.3.1 Considerations for wet gas flow metering 81
11.3.2 The adverse effects of contamination, hydrates, scale, and salts 82
11.3.3 Theoretical, laboratory and actual wet gas flow conditions 84
11.3.4 Undisclosed WGFM calculation procedures 84
11.3.5 Differential pressure measurement and wet gas flows 85
11.3.6 Problems due to lack of long time operating experience of WGFMs 86

Annex A (informative) WGFM design checklist 87

Annex B (informative) Wet gas parameters equations 89

Bibliography 90