

IEC/IEEE 80005-3:2025-12 (E)

Utility connections in port - Part 3: Low-voltage shore connection (LVSC) systems - General requirements

Contents	Page
FOREWORD.....	4
INTRODUCTION.....	6
1 Scope.....	7
2 Normative references.....	7
3 Terms and definitions.....	9
4 General requirements.....	11
4.1 System description.....	11
4.2 Distribution system.....	12
4.2.1 General.....	12
4.2.2 Equipotential bonding.....	13
4.3 Compatibility assessment before connection.....	13
4.4 LVSC system design and operation.....	13
4.4.1 System design.....	13
4.4.2 System operation.....	14
4.5 Personnel safety.....	14
4.6 Design requirements.....	14
4.6.1 General.....	14
4.6.2 Protection against moisture and condensation.....	14
4.6.3 Location and construction.....	14
4.6.4 Electrical equipment in hazardous areas.....	15
4.7 Electrical requirements.....	15
4.8 System study and calculations.....	16
4.9 Emergency shutdown including emergency-stop facilities.....	16
5 LV shore supply system requirements.....	17
5.1 Voltages and frequencies.....	17
5.2 Quality of LV shore supply.....	19
6 Shore-side installation.....	19
6.1 General.....	19
6.2 System component requirements.....	19
6.2.1 Shore-side main circuit-breaker.....	19
6.2.2 Shore power transformer.....	20
6.2.3 System earthing methodology.....	20
6.2.4 Protective earthing.....	20
6.2.5 Equipotential bonding.....	20
6.3 Shore-to-ship electrical protection system.....	21
6.4 LV safety protocol, interlocking and communication.....	22
6.4.1 General.....	22
6.4.2 Operating of the low-voltage (LV) circuit-breakers and disconnectors.....	22
6.5 Shore connection convertor equipment.....	22
6.5.1 General.....	22

6.5.2	Cooling	23
6.5.3	Protection	23
7	Ship-to-shore connection and interface equipment	23
7.1	General	23
7.2	Cable management system.....	24
7.2.1	General.....	24
7.2.2	Monitoring of cable tension or position	25
7.2.3	Monitoring of the cable length	25
7.3	Ship and shore couplers.....	26
7.3.1	General.....	26
7.3.2	Safety loop scheme.....	27
7.3.3	Pilot contacts.....	30
7.4	Ship-to-shore connection cable	30
7.5	Storage	30
8	Ship-side installation.....	30
8.1	General	30
8.2	Ship electrical distribution system.....	30
8.2.1	Short-circuit protection	30
8.2.2	Earth fault protection, monitoring and alarm.....	30
8.2.3	Distribution system earthing	31
8.3	Shore connection switchboard	31
8.3.1	General.....	31
8.3.2	Ship-side main circuit-breaker	31
8.3.3	Instrumentation and protection	31
8.3.4	Operation of the circuit-breaker	32
8.4	Onboard transformer.....	32
8.5	Onboard main switchboard	33
8.5.1	General.....	33
8.5.2	Circuit-breaker.....	33
8.5.3	Instrumentation.....	33
8.5.4	Protection	34
8.5.5	Operation of the circuit-breaker	35
8.6	Ship power restoration	35
9	LVSC system control and monitoring	35
9.1	General requirements.....	35
9.2	Load transfer via blackout.....	35
9.3	Load transfer via automatic synchronization	36
9.3.1	General.....	36
9.3.2	Protection requirements.....	36
10	Verification and testing.....	36
10.1	General	36
10.2	Initial tests of shore-side installation	37
10.2.1	General.....	37
10.2.2	Tests	37
10.3	Initial tests of ship-side installation	37
10.3.1	General.....	37
10.3.2	Tests	37

10.4	Tests of the LVSC system at the first call	38
10.4.1	General.....	38
10.4.2	Tests	38
11	Periodic tests and maintenance.....	38
11.1	General	38
11.2	Tests and verification of the LVSC system at repeated calls.....	39
12	Documentation	39
12.1	General	39
12.2	System description	39
Annex A	(informative) Shore-to-ship connection cable.....	40
A.1	General	40
A.2	Rated voltage.....	40
A.3	General design.....	40
A.3.1	General.....	40
A.3.2	Power and earth conductors.....	40
A.3.3	Pilot elements.....	41
A.3.4	Cabling	41
A.3.5	Separator tape.....	41
A.3.6	Outer sheath	42
A.3.7	Markings	42
A.4	Tests on complete cables	42
Annex B	(normative) Ship-to-shore cable management and connector	44
B.1	General	44
	Bibliography.....	46
	Figure 1 – Block diagram of a typical LVSC system.....	12
	Figure 2 – Phase sequence rotation – Positive direction.....	18
	Figure 3 – Balanced three-phase variables in time domain.....	18
	Figure 4 – Shore connection accessories.....	25
	Figure 5 – Safety circuit	28
	Figure A.1 – Bending test arrangement.....	43
	Figure B.1 – Contact assignment	44
	Table 1 – Number of parallel connections with the use of IEC 60309-5.....	26
	Table B.1 – Connector types.....	44