

ISO 23817:2026-08 (E)

Ships and marine technology - Ballast water management systems (BWMS) - Procedures for commissioning and testing BWMS using electrolytic methods

Contents	Page
Foreword	v
Introduction	vi
1 Scope	1
2 Normative references	1
3 Terms and definitions	1
4 Safety during commissioning	5
4.1 General	5
4.2 Safety training	6
4.2.1 General	6
4.2.2 Content of safety training	6
4.3 Personal protective equipment (PPE)	6
4.4 Ventilation	8
4.5 Fire-fighting and flooding handling	8
4.5.1 General	8
4.5.2 Firefighting	9
4.5.3 Flooding	9
5 Process of commissioning	10
6 Installation inspection	11
6.1 General	11
6.2 Tools for inspection	12
6.3 Component installation inspection	12
6.3.1 Major component location	12
6.3.2 Cooling arrangement	13
6.3.3 G2 sampling port location	13
6.4 Piping arrangement inspection	13
6.4.1 Piping route inspection	13
6.4.2 Piping material check	14
6.4.3 Air vent piping arrangement	14
6.5 Electrical wiring inspection	14
6.6 Component function verification	15
6.7 Deficiency handling	16
7 Function test	16
7.1 General	16
7.2 Preparation prior to function test	16
7.3 Alarm test	17
7.4 Bypass mode test	18
7.5 Emergency shutdown test	18
7.6 Independent shutdown test	19
7.7 Remote-control test	19
7.8 Ballasting treatment test	19
7.9 System design limitations (SDL) test	20
7.9.1 General	20
7.9.2 Low salinity test	20

7.9.3	Low temperature test	20
7.10	De-ballasting treatment test	20
7.11	Stripping treatment test	21
7.12	Test for multiple BWMS	21
7.13	Handling of ballasted water from testing	21
8	Commissioning test	21
8.1	General	21
8.2	Preparation prior to the commissioning testing	22
8.2.1	Preparation of ballast tank	22
8.2.2	Preparation of BWMS and associated shipboard systems	22
8.2.3	Responsibility of involved parties	22
8.2.4	Qualification of ballast water testing organization	23
8.3	Long cycle operation	24
8.3.1	General	24
8.3.2	Ballasting operation test	24
8.3.3	De-ballasting operation test	24
8.4	Collection of samples	25
8.5	Analysis of collected sample	25
8.5.1	General	25
8.5.2	Analysis method	25
8.6	Extracting BWMS operation logs	25
8.7	Reporting of biological efficacy verification	26
9	Documentation of commissioning	26
9.1	Confirmation record of commissioning procedures	26
9.2	Biological efficacy report	27
9.3	Training record	27
Annex A (informative)	Example of deficiency tracking	28
Annex B (informative)	Examples of records for performance evaluation of BWMS using electrolytic methods	29
Annex C (informative)	Examples of records for collection and analysis of samples	33
Annex D (informative)	Training of crew	35
Bibliography		36