

Contents

	Foreword
1	Scope
2	Normative references
3	Terms and definitions
4	Symbols and abbreviated terms
5	Installation requirements
5.1	Test apparatus and uncertainties of measurement
5.2	Test room for the airside and remote condenser
5.3	Installation and connection of the heat pump
5.4	Installation of heat pumps consisting of several parts
6	Setting and test conditions
6.1	General
6.2	Settings for non-ducted units
6.3	Setting the external static pressure difference for ducted units
6.4	Setting of units with integral pumps
6.5	Test conditions
7	Space heating test
7.1	Heating capacity test
7.2	Heating capacity correction
7.2.1	General
7.2.2	Capacity correction of fans for units without duct connection
7.2.3	Capacity correction due to indoor fan for ducted units
7.2.3.1	Units with integrated indoor fan
7.2.3.2	Units with non-integrated indoor fan
7.2.4	Capacity correction due to indoor liquid pump
7.2.4.1	Units with integrated liquid pump
7.2.4.2	Units with non-integrated liquid pump
7.2.4.3	Capacity correction for integrated glandless circulators
7.2.4.4	Capacity correction for integrated dry motor pumps
7.2.4.5	Capacity correction for non-integrated liquid pumps
7.2.5	Effective power input
7.2.5.1	General
7.2.5.2	Power input correction of fans for units without duct connection
7.2.5.3	Power input correction of fans for units with duct connection
7.2.5.3.1	Power input correction for integrated fans
7.2.5.3.2	Power input correction for non-integrated fans
7.2.5.4	Power input correction of liquid pumps
7.2.5.4.1	Power input correction for integrated liquid pumps
7.2.5.4.2	Power input correction for non-integrated liquid pumps
7.3	Test procedure
7.3.1	General
7.3.2	Preconditioning period
7.3.3	Equilibrium period
7.3.4	Data collection period
7.4	Heating capacity calculation
7.4.1	Steady state capacity test

7.4.2	Transient capacity test
7.5	Effective power input calculation
7.5.1	Steady state test
7.5.2	Transient with defrost cycle
7.5.3	Transient without defrost cycle
8	Test results and test report
8.1	Data to be recorded
8.2	Test report
9	Marking
Annex A (informative) Maximum and minimum operation	
A.1	General
A.2	Maximum operation
A.2.1	General
A.2.2	One-time heating heat pump water heater
A.2.3	Circulated heating heat pump water heater and static heating
A.3	Minimum operation
A.3.1	One-time heating minimum operation test
A.3.2	Circulated heating minimum operation test
A.3.3	Static heating minimum operation test
Annex B (normative) Heating capacity test procedures given in 7.2 and 7.3	
B.1	General
B.2	Step 1: Preconditioning
B.3	Step 2: Forced defrost cycle
B.4	Step 3: Equilibrium period
B.5	Step 4: Defrost cycle
B.6	Step 5: Data collection
B.7	Step 6: Variation of ΔT
B.8	Step 7: Steady state operation
B.9	Step 8: Transient operation
B.10	Step 8b
Annex C (normative) Determination of the liquid pump efficiency	
C.1	General
C.2	Hydraulic power of the liquid pump
C.2.1	The liquid pump is an integral part of the unit
C.2.2	The liquid pump is not an integral part of the unit
C.3	Efficiency of integrated pumps
C.3.1	Glandless circulators
C.3.2	Dry motor pumps
C.4	Efficiency of non-integrated pumps