

# DIN EN 14587-1:2019-08 (E)

Railway applications - Infrastructure - Flash butt welding of new rails - Part 1: R220, R260, R260Mn, R320Cr, R350HT, R350LHT, R370CrHT and R400HT grade rails in a fixed plant

---

<b>Contents</b>		<b>Page</b>
European foreword .....		4
Introduction .....		5
<b>1</b>	<b>Scope .....</b>	<b>6</b>
<b>2</b>	<b>Normative references .....</b>	<b>6</b>
<b>3</b>	<b>Terms and definitions .....</b>	<b>6</b>
<b>4</b>	<b>Requirements for the welding process .....</b>	<b>8</b>
4.1	General .....	8
4.2	Rail end preparation and horizontal alignment requirements .....	8
4.3	Clamping force .....	8
4.4	Pre-heating .....	8
4.5	Final flashing .....	8
4.6	Upsetting .....	8
4.7	Unclamping .....	8
4.8	Slippage .....	9
4.9	Welding parameters .....	9
4.10	Steps across the weld .....	9
4.11	Removal of excess upset .....	11
4.12	Post-weld thermal treatment .....	13
<b>5</b>	<b>Procedure approval .....</b>	<b>13</b>
5.1	General .....	13
5.2	Information to be supplied by the purchaser .....	13
5.3	Sample preparation .....	14
5.4	Approval tests .....	14
5.4.1	Visual examination .....	14
5.4.2	Weld trimming .....	14
5.4.3	Weld straightness and flatness .....	14
5.4.4	Magnetic particle or dye penetrant testing .....	14
5.4.5	Bend test .....	14
5.4.6	Macro examination .....	15
5.4.7	Micro examination .....	16
5.4.8	Hardness test .....	16
5.4.9	Fatigue test .....	16
5.5	Test report .....	17
<b>6</b>	<b>Approval of other rail profiles and grades .....</b>	<b>17</b>
6.1	General .....	17
6.2	Sample preparation .....	17
6.3	Approval tests .....	17
6.4	Test report .....	17
<b>7</b>	<b>Approval of the contractor .....</b>	<b>17</b>
7.1	General .....	17
7.2	Welding procedure .....	18

7.3	Operators .....	18
7.4	Supervision .....	18
7.5	Weld testing .....	18
7.6	Equipment .....	18
8	Weld production following procedure approval .....	18
8.1	Weld production .....	18
8.2	Information supplied by the purchaser .....	18
8.3	Rail end preparation and horizontal rail alignment requirements .....	19
8.4	Weld parameter monitoring .....	19
8.5	Weld identification .....	19
8.6	Visual examination .....	19
8.7	Steps across the weld .....	19
8.8	Finishing .....	19
8.8.1	Correction of vertical and horizontal weld alignment .....	19
8.8.2	Profile finishing of the rail head .....	19
8.9	Weld straightness and flatness .....	20
8.9.1	Alignment requirements .....	20
8.9.2	Straightness and flatness measurement .....	20
8.10	Bend test .....	21
8.10.1	General .....	21
8.10.2	Additional test requirements .....	21
8.10.3	Bend test procedure .....	21
8.10.4	Interpretation of results .....	22
8.10.5	Retesting .....	22
8.11	Documentation .....	22
Annex A (normative) Bend test requirements .....		23
Annex B (normative) Test weld fracture faces - Recording of defects .....		25
Annex C (normative) Fatigue test method for flash butt welds .....		27
C.1	General .....	27
C.2	Test equipment .....	27
C.3	Calibration .....	29
C.3.1	General .....	29
C.3.2	Test piece .....	29
C.4	Fatigue test method .....	29
C.4.1	General .....	29
C.4.2	Staircase test method .....	29
C.4.3	Example of the data analysis of a fatigue strength determination by the staircase method .....	32
C.4.4	Past-the-post test method .....	32
Annex D (normative) Macro examination and micro examination .....		34
D.1	Macro examination .....	34
D.2	Micro examination .....	34
Annex E (normative) Hardness testing .....		36
Bibliography .....		37