

DIN EN 13231-1:2024-01 (E)

Railway applications - Track - Acceptance of works - Part 1: Works on ballasted track - Plain line, switches and crossings

Contents		Page
European foreword		6
Introduction		8
1	Scope	9
2	Normative references	9
3	Terms and definitions	10
4	Acceptance of track works	14
4.1	General	14
4.2	Acceptance process	14
4.3	Acceptance procedure	15
4.3.1	Deadlines	15
4.3.2	Responsibilities	15
4.3.3	Preliminary procedure to the acceptance	15
4.3.4	Results of the acceptance process	15
4.3.5	Warranty	16
5	Acceptance of plain line, switches and crossings and rail expansion devices - new track and renewal	16
5.1	General	16
5.2	Substructure works	17
5.3	Track geometry quality	19
5.4	Absolute track position	21
5.5	Working parameters of on track machines (OTMs)	21
5.5.1	General	21
5.5.2	Tamping	21
5.5.3	Ballast compaction and stabilization works	23
5.5.4	Ballast replacement/cleaning works	24
5.6	Track components	25
5.6.1	General	25
5.6.2	Rails	25
5.6.3	Welds	25
5.6.4	Mechanical rail joints	25
5.6.5	Insulated rail joints	25
5.6.6	Rail fastening systems	26
5.6.7	Sleepers and bearers	27
5.6.8	Sleeper spacing	27
5.6.9	Bearer spacing	27
5.6.10	Out of squareness of sleepers and bearers	27
5.6.11	Voiding of sleepers and bearers	28
5.6.12	Rail anchor	28
5.6.13	Sleeper anchor	28
5.6.14	Ballast	28
5.6.15	Under ballast mat	29
5.6.16	Substructure material	29
5.7	Ballast cross section	29
5.8	Structure gauge	30
5.9	Neutralization works	30

5.9.1	General	30
5.9.2	Specification of the stress-free temperature	31
5.9.3	Neutralization of rails	31
5.10	Measurements and quality checks for switches and crossings and rail expansion devices	31
5.10.1	General	31
5.10.2	Verification of positioning of rail parts for switches and crossings and rail expansion devices	32
5.10.3	Verification of functional and safety dimensions for switches and crossings and rail expansion devices	38
5.10.4	Verification of gaps for switches and crossings and rail expansion devices	49
5.10.5	Quality checks for switches and crossings and rail expansion devices	52
5.10.6	Verification of safety and functionality of switches and crossings with moveable parts ...	52
6	Acceptance of plain line, switches and crossings and rail expansion devices - Maintenance	53
6.1	General	53
6.2	Machine tamping - maintenance measure	53
6.2.1	General	53
6.2.2	Preliminary works	53
6.2.3	Track geometry quality	54
6.2.4	Absolute track position	56
6.2.5	Working parameters of on track machines (OTM)	56
6.2.6	Track components	56
6.2.7	Ballast cross section	56
6.2.8	Structure gauge	56
6.2.9	Measurements and quality verifications for switches and crossings and rail expansion devices	56
6.3	Ballast cleaning - maintenance measure	56
6.3.1	General	56
6.3.2	Preliminary works	56
6.3.3	Ballast replacement and cleaning works	56
6.4	Hand tamping and manual geometry correction - maintenance measure	57
6.5	Replacement of track components (fastener and sleeper) - maintenance measure.57 6.6 (Local) Spot ballast replacement - maintenance measure	57
6.7	Neutralization works - maintenance measure	57
6.8	Works in switches and crossings and rail expansion devices - maintenance measure	57
6.8.1	General	57
6.8.2	Verification of functional and safety dimensions for switches and crossings and rail expansion devices	57
6.8.3	Verification of gaps for switches and crossings and rail expansion devices	59
6.8.4	Quality checks for switches and crossings and rail expansion devices	62
	Annex A (normative) Measuring systems - Requirements and documentation	63
A.1	General	63
A.2	Track geometry	63
A.2.1	General	63
A.2.2	Measurement devices	63
A.2.3	Measurement methods	63
A.3	Absolute track position	64
A.3.1	General	64
A.3.2	Network of survey points and reference systems	64
A.3.3	Specifications for geodetic measurements	65
A.3.4	Measuring systems	66
A.4	Working parameters of on track machines	66
A.4.1	General	66
A.4.2	Quality control factors of tamping works	66
A.4.3	Ballast compaction and stabilization - mechanical stabilization tools	67
A.4.4	Ballast replacement/cleaning works	68
A.5	Track components	69
A.5.1	Welds	69

A.5.2	Rail fastening system	69
A.5.3	Sleeper spacing	70
A.5.4	Bearer spacing	70
A.5.5	Out of squareness of the sleepers	70
A.5.6	Voiding of sleepers and bearers	70
A.6	Ballast cross section	70
A.7	Structure gauge check	70
A.7.1	General	70
A.7.2	Data acquisition	70
A.7.3	Assessment	71
A.7.4	Acceptance of the clearance of the structure gauge	71
A.8	Neutralization works	72
A.8.1	General	72
A.8.2	Neutralization of rails	72
Annex B (normative) Requirements for measuring systems for switches and crossings and rail expansion devices		74
B.1	General	74
B.2	Special design	74
B.3	Requirements and accuracy of the measurement equipment	76
B.4	Specific measurements	84
Annex C (informative) Relationship between D1 values and chord values for LL and AL (based on statistical evaluation)		85
C.1	General	85
C.2	Comparison method	85
C.3	Results	87
C.4	Conclusions	89
Bibliography		90