

DIN EN 1997-1:2014-03 (E)

Eurocode 7: Geotechnical design - Part 1: General rules

Contents

Page

Foreword to EN 1997-1:2004	5
Foreword to EN 1997-1:2004/A1:2013	5
Section 1 General	9
1.1 Scope	9
1.2 Normative references.....	10
1.3 Assumptions.....	11
1.4 Distinction between Principles and Application Rules	11
1.5 Definitions	12
1.6 Symbols	13
Section 2 Basis of geotechnical design	20
2.1 Design requirements.....	20
2.2 Design situations.....	22
2.3 Durability	23
2.4 Geotechnical design by calculation.....	24
2.5 Design by prescriptive measures.....	36
2.6 Load tests and tests on experimental models	37
2.7 Observational method	37
2.8 Geotechnical Design Report	37
Section 3 Geotechnical data	39
3.1 General	39
3.2 Geotechnical investigations	39
3.3 Evaluation of geotechnical parameters.....	40
3.4 Ground Investigation Report.....	48
Section 4 Supervision of construction, monitoring and maintenance	50
4.1 General	50
4.2 Supervision	50
4.3 Checking ground conditions.....	52
4.4 Checking construction.....	53
4.5 Monitoring	54
4.6 Maintenance.....	55
Section 5 Fill, dewatering, ground improvement and reinforcement	56
5.1 General	56
5.2 Fundamental requirements	56
5.3 Fill construction	56
5.4 Dewatering	60
5.5 Ground improvement and reinforcement	61
Section 6 Spread foundations	62
6.1 General	62
6.2 Limit states	62
6.3 Actions and design situations	62
6.4 Design and construction considerations	62
6.5 Ultimate limit state design	63
6.6 Serviceability limit state design	66
6.7 Foundations on rock; additional design considerations	68
6.8 Structural design of spread foundations	69
6.9 Preparation of the subsoil	69

Section 7	Pile foundations	71
7.1	General	71
7.2	Limit states	71
7.3	Actions and design situations	71
7.4	Design methods and design considerations	73
7.5	Pile load tests	75
7.6	Axially loaded piles	77
7.7	Transversely loaded piles	87
7.8	Structural design of piles	89
7.9	Supervision of construction	89
Section 8	Ⓐ₁ Anchors Ⓐ₁	92
8.1	General	92
8.2	Limit states	93
8.3	Design situations and actions	94
8.4	Design and construction considerations	94
8.5	Limit state design of anchors	95
8.6	Tests on anchors	98
8.7	Lock-off load for pre-stressed anchors	99
8.8	Supervision, monitoring and maintenance	99
Section 9	Retaining structures	100
9.1	General	100
9.2	Limit states	100
9.3	Actions, geometrical data and design situations	101
9.4	Design and construction considerations	104
9.5	Determination of earth pressures	105
9.6	Water pressures	108
9.7	Ultimate limit state design	108
9.8	Serviceability limit state design	112
Section 10	Hydraulic failure	114
10.1	General	114
10.2	Failure by uplift	115
10.3	Failure by heave	117
10.4	Internal erosion	117
10.5	Failure by piping	118
Section 11	Overall stability	120
11.1	General	120
11.2	Limit states	120
11.3	Actions and design situations	120
11.4	Design and construction considerations	121
11.5	Ultimate limit state design	122
11.6	Serviceability limit state design	124
11.7	Monitoring	124
Section 12	Embankments	126
12.1	General	126
12.2	Limit states	126
12.3	Actions and design situations	126
12.4	Design and construction considerations	127
12.5	Ultimate limit state design	128
12.6	Serviceability limit state design	129
12.7	Supervision and monitoring	129
Annex A	(normative) Ⓐ₁ Partial and correlation factors for ultimate and serviceability limit states and recommended values Ⓐ₁	131
Annex B	(informative) Background information on partial factors for Design Approaches 1, 2 and 3	143
Annex C	(informative) Sample procedures to determine earth pressures	146
Annex D	(informative) A sample analytical method for bearing resistance calculation	162

Annex E (informative) A sample semi-empirical method for bearing resistance estimation 165

Annex F (informative) Sample methods for settlement evaluation 166

Annex G (informative) A sample method for deriving presumed bearing resistance for spread foundations on rock 168

Annex H (informative) Limiting values of structural deformation and foundation movement..... 170

Annex J (informative) Checklist for construction supervision and performance monitoring..... 172