DIN EN 16907-6:2019-04 (E)

Earthworks - Part 6: Land reclamation earthworks using dredged hydraulic fill

Contents

Page

European foreword 5

Introduction 6

1 Scope 7

2 Normative references 7

3 Terms and definitions 9

4 Symbols and abbreviations 13

5 Stages of land reclamation projects 13

6 Design aspects for earthworks with dredged hydraulic fill 14
6.1 Introduction 14
6.2 Basis of Design 14
6.2.1 General 14
6.2.2 Scope of Work 15
6.2.3 The project site 15
6.2.4 Standards and Codes of Practice 15
6.2.5 Functional requirements 15
6.2.6 Boundary conditions and constraints 15
6.2.7 Performance requirements 16
6.2.8 Site data 16
6.2.9 Borrow area 16
6.2.10 Environmental constraints 17
6.2.11 Regulations, permits and licenses 17
6.3 General design aspects 17
6.3.1 Earth-structure design aspects 17
6.3.2 Morphological and environmental aspects 17
6.4 Boundary conditions affecting the execution 18
6.4.1 General 18
6.4.2 Locations of land reclamation area, borrow area and disposal site 18
6.4.3 Soil conditions at the land reclamation area 18
6.4.4 Soil conditions at the borrow area 18
6.4.5 Suitable fill material properties 19
6.4.6 Dredging close to existing structures 19
6.4.7 Construction tolerances 19
6.4.8 Return of process water 19
6.4.9 Ground improvement of the fill mass and the subsoil 19
6.4.10 Project execution time and milestones 19
6.5 Earthworks design considerations 20
6.5.1 Introduction 20
6.5.2 Land reclamation area 20
6.5.3 Borrow area 20
6.5.4 Available quantity of suitable fill material 21
6.6 Design considerations in relation to dredging equipment 22

7 Technical specifications for earthworks with dredged hydraulic fill 22
7.1 Introduction 22

7.2 Technical specifications for the subsoil 22
7.3 Technical specifications for the fill mass 22
7.4 Technical specifications for the fill material 23

8 Data collection 23
8.1 General 23
8.2 Bathymetrical and topographical data 24
8.3 Geotechnical and geophysical data 24
8.3.1 General 24
8.3.2 Geotechnical and geophysical data in the borrow area 24
8.3.3 Geotechnical and geophysical data in the land reclamation area 26
8.4 Hydrological and meteorological data 26
8.5 Seismic data 27
8.6 Morphological and environmental data 27
8.6.1 General 27
8.6.2 Sediment transport 27
8.6.3 Total Suspended Solids (TSS) and turbidity 28
8.6.4 Organic matter and gas 28
8.6.5 Contaminants 28
8.6.6 Underwater sound 28
8.7 Seabed features 28
8.8 Site constraints 29

9 Equipment 30
9.1 Selection of the dredging equipment 30
9.1.1 General 30
9.1.2 Selection of the dredging equipment based on the capabilities of the equipment 30
9.1.3 Selection of the dredging equipment based on hydraulic and meteorological conditions 30
9.1.4 Selection of the dredging equipment based on the presence of shipping 31
9.1.5 Selection of the dredging equipment based on environmental restrictions 31
9.2 Typical dredging equipment 31
9.3 Accuracy and tolerances 32
9.4 Minimal vessel requirements for monitoring and data logging 32

10 Design of the execution of earthworks with dredged hydraulic fill 33
10.1 Construction 33
10.1.1 General 33
10.1.2 Preparation phase 33
10.1.3 Construction phase 34
10.1.4 Post-construction phase 35
10.2 Selection of placement method 35
10.3 Preparation of the seabed for dredging and for the land reclamation works 37
10.4 Containment bunds 38
10.5 Process water management 39
10.6 Water table in the land reclamation area 39
10.7 Use of cohesive or fine grained materials 39
10.8 Ground improvement 39

11 Quality control 40
11.1 General 40
11.2 Quality Control Plan 40
11.3 Monitoring and testing 41
11.4 Dimensions and boundary conditions 41

11.4.1 Borrow area **41**
11.4.2 Land reclamation area **42**
11.5 Quality of the fill material **42**
11.5.1 Source material in borrow area **42**
11.5.2 Fill material in land reclamation area **42**
11.6 Fill mass **42**
11.6.1 Bearing capacity **42**
11.6.2 Slope stability **43**
11.6.3 Consolidation and deformations **43**
11.6.4 *In situ* density and density index **43**
11.6.5 Permeability **45**
11.6.6 Frequency of testing **45**
11.6.7 Environmental monitoring **46**
11.7 Handover documentation **47**
Annex A (informative) Non EN and non ISO test and monitoring methods **48**
A.1 General **48**
A.2 Electrical piezometer **49**
A.3 Inclinometer **49**
A.4 Rod and plate settlement gauges **49**
A.5 Settlement profiling tube **50**
A.6 Trial embankment **50**
A.7 Zone Loading Test **51**
Annex B (informative) Determination of minimum and maximum dry densities and density index **52**
B.1 General **52**
B.2 British Standard procedures **52**
B.2.1 General **52**
B.2.2 Minimum dry density of sands **52**
B.2.3 Minimum dry density of gravelly soils **53**
B.2.4 Maximum dry density of sands **53**
B.2.5 Maximum dry density of gravelly soils **53**
B.3 ASTM procedures **53**
B.3.1 General **53**
B.3.2 Minimum index dry density **53**
B.3.3 Maximum index dry density **54**
B.4 Density index **54**
Bibliography **55**