DIN EN 16907-4:2019-04 (E)

Earthworks - Part 4: Soil treatment with lime and/or hydraulic binders

Contents

Page

European foreword 6

Introduction 7

1 Scope 9

2 Normative references 9

3 Terms and definitions 11

4 Symbols and abbreviations 14

5 Constituents 15
5.1 Materials 15
5.1.1 General 15
5.1.2 Natural soils and processed aggregates 15
5.1.3 Low strength, intermediate strength and high strength rocks, and chalk 15
5.1.4 Recycled materials 15
5.1.5 Artificial materials 15
5.2 Binders 15
5.2.1 Cement 15
5.2.2 Fly ash 16
5.2.3 Slag 16
5.2.4 Hydraulic road binder 16
5.2.5 Lime 16
5.2.6 Blends 16
5.3 Water 16
5.4 Other constituents 16

6 Mixtures 16
6.1 General 16
6.2 Proportioning 16

7 Laboratory testing methodology 17
7.1 General 17
7.2 Identification tests 17
7.2.1 Identification of the materials to be treated 17
7.2.2 Identification of the binders 17
7.3 Feasibility of treatment 17
7.4 Workability period 18
7.5 Characteristics for execution 18
7.5.1 Improvement 18
7.5.2 Stabilization 18
7.6 Mechanical performance 19
7.6.1 Curing conditions 19
7.6.2 Resistance to water 19
7.6.3 Strength for direct construction trafficking 19
7.6.4 Resistance to frost 19
7.6.5 Performance classification testing 19
7.6.6 Other performance tests 20
7.7 Preparation of the specimens 20
7.7.1 Particle size of the material 20

7.7.2 Production of the mixtures 20
7.7.3 Dimensions of the specimens 20
7.7.4 Compaction procedures 20
7.7.5 Curing 21
7.8 Content of the laboratory studies 21
7.8.1 General 21
7.8.2 Identification of the constituents 21
7.8.3 Improvement 21
7.8.4 Stabilization 21
7.9 Laboratory testing report 22

8 Performance classification of the mixtures 23
8.1 General 23
8.2 Improvement 23
8.2.1 General 23
8.2.2 Immediate bearing index 24
8.2.3 Moisture condition value 24
8.2.4 Degree of compaction 24
8.2.5 Swelling 25
8.3 Stabilization 25
8.3.1 Requirements for the fresh mixture 25
8.3.2 Laboratory mechanical performance classification 28
8.3.3 Resistance to water 32
8.3.4 Strength for direct construction trafficking 34
8.3.5 Resistance to frost 34
8.3.6 Other performance 34

9 Execution and control 34
9.1 Introduction 34
9.1.1 General 34
9.1.2 Prerequisites 34
9.2 Preliminary engineering check 35
9.2.1 General 35
9.2.2 Site investigation 35
9.2.3 Sulfide, sulfate, organic matter and other deleterious materials 35
9.2.4 Influential parameters 36
9.2.5 Prior laboratory testing 36
9.3 Binders 36
9.4 Soil treatment plant types 36
9.5 Soil improvement 37
9.5.1 General 37
9.5.2 Materials suitable for improvement 37
9.5.3 Improvement during excavation 37
9.5.4 Improvement in fill area 37
9.5.5 Binder spreading 37
9.5.6 *In situ* mixing 38
9.5.7 Compaction 38
9.5.8 Protection of the works 38
9.5.9 Climatic considerations 38
9.6 Soil stabilization 38
9.6.1 General 38
9.6.2 Material suitable for stabilization 39
9.6.3 Soil preparation 39
9.6.4 Stabilization processes for capping and embankment 40

9.6.5 Other applications 42
9.6.6 Layer Interface and organization of the work 42
9.7 Testing and Compliance 43
9.7.1 Specification 43
9.7.2 Compliance tests and records 43
9.7.3 Completion reports 45
9.8 Climatic and practical considerations 46
Annex A (informative) Production of test specimens for treated materials 47
A.1 Introduction 47
A.2 Sampling 47
A.3 Water content 47
A.4 Maximum size of the particles 47
A.5 Treatment 48
A.6 Mellowing and compaction of the treated material in the specimen mould 49
A.7 Curing and storage 49
A.8 Removing sample from the mould 50
A.9 Reporting 51
Annex B (informative) Loading speed for the strength and modulus tests 52
Annex C (informative) Non destructive seismic test method for mechanical performance 54
C.1 Introduction 54
C.2 Scope 54
C.3 Test apparatus 54
C.4 Definitions and theoretical approach 55
C.5 Principle of test method 56
C.6 Significance and use 56
C.7 Measurement 57
C.8 References 59
Annex D (informative) Example of evaluation of performance variability of treated soil as a result of variation during implementation Binder percentage adjustment and method for compensating it 60
Annex E (informative) Examples of age of classification and curing regimes for mechanical performance of treated materials for earthworks 62
Annex F (informative) Other performance characteristics for treated materials 63
Annex G (informative) Field and laboratory identifications of common sulfide and sulfate minerals 64
G.1 Field Identification 64
G.2 Laboratory Identification 64
G.3 References 65
Annex H (informative) Soil Treatment Plant Types 66

H.1 General **66**
H.2 Binder storage units **66**
H.3 Binder spreading units **66**
H.4 Soil preparation plant **67**
H.5 *In situ* mixing plant **67**
H.6 Fixed or semi mobile mixing plants **69**
H.7 Water bowsers **71**
H.8 Compaction plant **71**
Annex I (informative) Treatment sequence and processes **72**
Annex J (informative) Other applications for stabilized materials **78**
J.1 General **78**
J.2 Filling in narrow places **78**
J.3 Construction of lower layers in high embankments built with water sensitive soils or evolutive rocks which may be subject to occasional flooding. **79**
J.4 Steepened slopes of embankment **79**
J.5 Slope repairs **80**
J.6 Reinforced slopes **80**
J.7 Foundations **80**
J.8 Load transfer platforms **80**
J.9 Water retaining structures **81**
J.10 Contaminated soils **81**
Annex K (informative) Site Stabilization checklist **82**
Annex L (informative) Safety considerations **85**
L.1 General **85**
L.2 Specific protective equipment **85**
Annex M (informative) Climatic and practical considerations **86**
M.1 General **86**
M.2 Weather **86**
M.3 Binder dust emission **87**
M.4 Run off and leachate **88**
Annex N (informative) Method and charts to determine the quantity of lime needed to reach a targeted IPI value **89**