ISO 16924:2016-12 (E)

Natural gas fuelling stations - LNG stations for fuelling vehicles

Contents

Page

Foreword vii

1 Scope 1

2 Normative references 1

3 Termsanddefinitions 2

4 Abbreviated terms 9

5 Risk management 10
5.1 Risk assessment 10
5.1.1 General 10
5.1.2 Protection against overpressure 10
5.1.3 Static electricity 11
5.2 Fire protection 11
5.2.1 Hazardous area classification 11
5.2.2 Sources of ignition 11
5.2.3 Fire fighting 12
5.3 Explosion protection measures 12

6 General design requirements 12
6.1 General 12
6.1.1 Design philosophy 12
6.1.2 Buildings and civil works 13
6.1.3 Installation and construction 14
6.2 Site layout 15
6.2.1 Separation distances 15
6.2.2 Traffic management 15
6.2.3 Security 15
6.2.4 Requirements for location of equipment 15
6.3 Environmental considerations 16
6.3.1 Noise attenuation 16
6.3.2 Prevention of venting of natural gas 16

7 Fuel supply to the fuelling station 16
7.1 Application 16
7.2 Equipment compatibility 16
7.3 Filling connector 17
7.4 Requirements for filling 17
7.4.1 General requirements 17
7.4.2 Prevention of overpressurization and overfilling 17
7.5 Prevention of back flow 17
7.6 Bleed connections 17
7.7 Draining of liquid from the LNG storage tank 18
7.8 LNG tanker 18
7.8.1 Immobility 18
7.8.2 Anti-drive-away equipment 18
7.8.3 Turning off the engine 18
7.8.4 Equalizing the potentials 18

8 Storage 18

8.1 LNG storage 18
8.1.1 Design and construction 18
8.1.2 Safety requirements 20
8.1.3 Installation guidance 24
8.2 CNG buffer storage 25

9 Pumps and compressors 25
9.1 Connection of LNG pumps to the LNG storage tank 25
9.1.1 General 25
9.1.2 NPSH requirements 25
9.1.3 Vapour return 25
9.1.4 Protection against weather 25
9.1.5 Accessibility 26
9.2 LNG centrifugal pump (including ancillaries) 26
9.2.1 General provisions 26
9.2.2 Liquid inlet to the centrifugal pump 26
9.2.3 Centrifugal pump design 26
9.2.4 Vibration 26
9.2.5 Detection of shaft seal leak 27
9.2.6 Detection of cavitation 27
9.3 LNG reciprocating pump for LCNG fuelling stations (including ancillaries) 27
9.3.1 General provisions 27
9.3.2 Liquid supplied to the reciprocating pump 27
9.3.3 Design 27
9.3.4 Vibration 27
9.3.5 Pulsation 27
9.4 Commonalities for LNG centrifugal and reciprocating pumps 27
9.4.1 Suction line 27
9.4.2 Instrumentation 28
9.4.3 Markings of a pump 28
9.4.4 Instructions 28
9.5 Natural gas compressor 29

10 Dispensers 29
10.1 LNG dispensers 29
10.1.1 General requirements 29
10.1.2 Breakaway system 31
10.1.3 Fuelling hoses 31
10.1.4 Fuelling nozzles 32
10.1.5 Dispenser enclosure 32
10.1.6 Other requirements 33
10.2 CNG dispensers 33

11 Vaporizers and heaters 34
11.1 Application 34
11.2 Design of vaporizers and heaters 34
11.3 Ambient air vaporizer 35
11.3.1 General 35
11.3.2 Defrosting 35
11.3.3 Aluminium vaporizers 35
11.4 Electric vaporizer/heater 35
11.5 Water bath vaporizer 36
11.6 Fired vaporizers 36
11.7 Remotely heated vaporizers 36

12 Odorization 36
12.1 General requirements 36
12.2 High-pressure odorizer 37
12.3 Safety 37
12.4 Monitoring 37
12.5 Odorant 38

12.6 Dynamics of function 38

13 Pipework 38
13.1 General 38
13.2 Pipework design 38
13.2.1 General 38
13.2.2 Overground pipework 39
13.2.3 Underground pipework 39
13.2.4 Pipework in ducts 39
13.2.5 Flexible connections 40

14 Electrical equipment and wiring 40
14.1 General 40
14.2 Main considerations 40
14.2.1 Grounding 40
14.2.2 Lightning 40
14.2.3 Contact with live parts 40
14.2.4 Cables 40
14.2.5 Static electricity 41
14.3 Other considerations 41
14.3.1 Interface 41
14.3.2 Primary seal 41
14.3.3 Additional seal 41
14.3.4 Conduit seals 41
14.3.5 Detection vents 42

15 Instrumentation and control system 42
15.1 General 42
15.2 Gas detectors 42
15.3 Flame detectors 42
15.4 Pressure gauges 42
15.5 Temperature sensors 42
15.6 Manual emergency shutdown devices 42
15.7 Emergency power supply unit 43

16 Emergency shutdown 43
16.1 Application 43
16.2 Procedure 43
16.3 Activation 43
16.4 ESD action 43
16.5 Reset 44

17 Specialconfigurations 44
17.1 Movable LNG fuelling station 44
17.1.1 General requirements 44
17.1.2 Anchoring 44
17.1.3 Containment 44
17.2 Mobile LNG fuelling station 44
17.2.1 General requirements 44
17.2.2 Anchoring 45
17.2.3 Containment 45
17.2.4 Design 45
17.2.5 Additional requirements for operation 45

18 Testing and commissioning 45
18.1 Testing 45
18.1.1 Electrical testing 45
18.1.2 Pressure strength testing 46
18.1.3 Leak testing 46
18.2 Commissioning 46
18.2.1 General provisions 46
18.2.2 Purging 47

18.2.3 Functional testing 47
18.2.4 First filling of the LNG storage tank and other components 47

19 Operations 47
19.1 LNG tanker offloading 47
19.2 Fuelling procedure 47
19.3 Safety signs 48
19.3.1 General on identification labels 48
19.3.2 Equipment marking 48
19.4 Equipment and pipework identification 49
19.5 Training 49
19.6 Installation and operating instructions 50
19.7 Emergency plan 51
19.8 Maintaining the emergency shutdown 51

20 Inspection and maintenance 51
20.1 Inspection 51
20.1.1 General requirements 51
20.1.2 Inspection and testing of electrical systems 52
20.1.3 Inspection and re-testing of the safety relief valves 52
20.1.4 Safety and fire protection equipment 53
20.2 Maintenance 53
20.2.1 Preventive maintenance planning 53
20.2.2 Maintenance procedures 53
20.2.3 Maintenance safety 53
20.2.4 Draining of the LNG storage tank 54

Annex A (informative)Examplesofhazardouszonesclassification 55

Annex B (normative) Separation distances 59

Annex C (informative)ExampleflowdiagramofanLNGfuellingstation 63

Annex D (informative)ExampleflowdiagramofanLCNGfuellingstation 64

Annex E (informative)ExampleflowdiagramofanLNGandLCNGfuellingstation 65

Annex F (informative) Process requirements for the effective cryogenic pump operation 66

Annex G (informative) Recommendations for installation of a centrifugal pump 68

Annex H (informative) Recommendations for centrifugal pump design 69

Annex I (informative) Recommendations for installation of a reciprocating pump 70

Annex J (informative) Recommendations on the content of the cryogenic pump operation instructions 72

Annex K (informative)Exampleflowdiagramofahigh-pressureodorizer 74

Annex L (informative)LNGidentificationmarkofanLNGfuellingstation 75

Bibliography 76