

# ISO 20257-2:2021 (E)

## Installation and equipment for liquefied natural gas — Design of floating LNG installations — Part 2: Specific FSRU issues

---

### Contents

	Foreword
1	Scope
2	Normative references
3	Terms, definitions and abbreviated terms
3.1	Terms and definitions
3.2	Abbreviated terms
4	Basis of design
4.1	General description of FSRU
4.2	Main design criteria for process facilities
4.3	Reliability, availability and maintainability of LNG floating installation
4.4	Specific requirements for FSRU operating as LNG carrier
4.5	Specific FSRU studies
4.5.1	General
4.5.2	Environmental impact of seawater intake and discharge study
4.5.3	Recirculation study
4.5.4	Scour protection study
5	Specific health, safety and environmental issues
5.1	General
5.2	Environmental considerations related to water heating and cooling issues
5.3	Safety considerations
5.3.1	General requirements
5.3.2	Layout constrains
5.3.3	Layout constraints with respect to surroundings
5.3.3.1	Applicability
5.3.3.2	Qualitative analysis
5.3.3.3	Confirmation by calculation
5.3.4	Layout constraints with respect to facility arrangement
5.3.4.1	Qualitative analysis
5.3.4.2	Confirmation by calculation
5.3.5	Risk prevention measures
5.3.5.1	General
5.3.5.2	Active fire protection
5.3.5.2.1	Active fire protection philosophy
5.3.5.2.2	Systems design
5.3.5.2.3	Water systems
5.3.5.2.4	Foam systems
5.3.5.2.5	Dry chemicals systems
5.3.5.3	Fire, cold spill and gas detection system
5.3.5.4	Drainage systems
5.3.5.5	Emergency response
5.3.5.6	Safety integrity levels
6	Mooring and stationkeeping
7	Hull design
8	LNG storage
8.1	Specific requirements for cargo tank pressure management

- 8.2 Specific requirements for LNGC overpressure protection
- 8.3 Rollover risk
- 9 Transfer systems
  - 9.1 General
  - 9.2 Send-out natural gas: NG gas transfer requirements
    - 9.2.1 Functional requirements
    - 9.2.2 Transfer systems design
      - 9.2.2.1 Composition
      - 9.2.2.2 Articulated piping solutions
      - 9.2.2.3 Flexible pipe solutions
    - 9.2.3 Emergency disconnection
      - 9.2.3.1 Quantitative risk analysis inputs
      - 9.2.3.2 Emergency disconnection system
      - 9.2.3.3 Flange-to-flange connection
    - 9.2.4 Operating envelope
      - 9.2.4.1 General
      - 9.2.4.2 Operating of transfer systems equipped with EDS
      - 9.2.4.3 Operating of transfer systems not equipped with EDS
  - 9.3 LNG sampling
- 10 BOG handling and recovery
  - 10.1 General
  - 10.2 LNG tank design pressure flexibility
  - 10.3 Specific requirements for recondenser
  - 10.4 Specific requirements for gas compressors
    - 10.4.1 General
    - 10.4.2 Specific functional requirements for LD compressors
    - 10.4.3 Specific functional requirements for HD compressors
    - 10.4.4 Specific functional requirements for HP or MSO compressors
- 11 Regasification equipment requirements
  - 11.1 LNG pumps
    - 11.1.1 General
    - 11.1.2 Functional requirements
    - 11.1.3 Materials selection
    - 11.1.4 In-tank LNG pump
    - 11.1.5 HP LNG pump
  - 11.2 LNG vaporization system
    - 11.2.1 Functional requirements
    - 11.2.2 Vaporization type
    - 11.2.3 Materials selection
    - 11.2.4 Protective coating
    - 11.2.5 Marine growth
    - 11.2.6 Stability/vibration
    - 11.2.7 Safety relief valves
  - 11.3 Trim heater
  - 11.4 Venting from regasification systems
- 12 Gas send out
  - 12.1 High integrity pressure protection system
    - 12.1.1 Send-out pressure control
    - 12.1.2 Typical description of HIPPS
    - 12.1.3 Design requirements for HIPPS
  - 12.2 Send-out gas metering
    - 12.2.1 Uses of send-out gas metering
    - 12.2.2 Measurement devices type
    - 12.2.3 Accuracy
    - 12.2.4 External influences
    - 12.2.5 Gas chromatograph – Gas analyser
    - 12.2.6 Sparing philosophy
    - 12.2.7 Z-configuration
  - 12.3 Odorization systems

- 13 Utilities**
  - 13.1 General**
  - 13.2 Cooling and heating medium**
    - 13.2.1 Cooling medium**
      - 13.2.1.1 General**
      - 13.2.1.2 Seawater for equipment**
      - 13.2.1.3 Freshwater for equipment**
    - 13.2.2 Heating medium**
      - 13.2.2.1 Seawater**
      - 13.2.2.2 Steam**
    - 13.2.3 Nitrogen system**
    - 13.2.4 Fuel gas**
- 14 Process and safety control systems**
  - 14.1 General requirements**
  - 14.2 Interfaces between FSRU and gas export connection**
  - 14.3 Communication onshore/offshore**
- 15 Security management**
- 16 Commissioning**
- 17 Inspection and maintenance**
  - 17.1 General requirements**
  - 17.2 Cargo tank**
  - 17.3 In-tank LNG pump**
  - 17.4 Regasification equipment**
    - 17.4.1 HP LNG pump**
    - 17.4.2 LNG vaporizer**
  - 17.5 Recondenser**
  - 17.6 Handling/Crane equipment**
- 18 Preservation and corrosion protection**
- 19 Conversion of existing unit to floating LNG installations**
- Annex A (informative) Regasification system description**
  - A.1 General**
  - A.2 Open loop (direct contact) vaporizer**
  - A.3 Open loop (intermediate fluid) vaporizer**
  - A.4 Closed loop vaporizer**
  - A.5 Combined vaporizers**
  - A.6 Ambient air vaporizers**

Page count: 40