

# ISO 8528-6:2023-11 (E)

## Reciprocating internal combustion engine driven alternating current generating sets - Part 6: Test methods

---

<b>Contents</b>		<b>Page</b>
Foreword .....		v
1	Scope .....	1
2	Normative references .....	1
3	Terms, definitions and abbreviations .....	2
3.1	Terms and definitions .....	2
3.2	Abbreviated terms .....	7
4	Other regulations and additional requirements .....	8
5	General test requirements .....	8
5.1	General .....	8
5.2	Measurement equipment accuracy .....	9
6	Functional test .....	10
6.1	General .....	10
6.1.1	General .....	10
6.1.2	Physical functional test .....	10
6.1.3	Functional test by simulation .....	10
6.2	General inspection .....	10
6.3	Measurements .....	11
6.4	Functional test report .....	11
7	Type test .....	12
7.1	General .....	12
7.2	Testing conditions .....	12
7.3	Characterisation of performance class .....	13
7.3.1	Steady state verification at constant power .....	13
7.3.2	Verification of power-sharing capability .....	14
7.3.3	Step load test .....	15
7.3.4	Start and stop time characteristics .....	16
7.4	Reactive power capability .....	18
7.4.1	General .....	18
7.4.2	Verification of reactive power capability .....	18
7.4.3	Test method for verification of reactive power capability control methods .....	20
7.5	Verification of grid synchronization limits .....	24
7.5.1	General .....	24
7.5.2	Testing method for verification of grid synchronisation limits .....	24
7.6	Test method for verification of FRT capability .....	25
7.6.1	General .....	25
7.6.2	Aim of the test .....	25
7.6.3	Documents to be provided before test .....	25
7.6.4	Test method .....	26
7.6.5	Acceptance criteria .....	27
7.7	Test method for verification of active power response to frequency variation .....	27
7.7.1	General .....	27
7.7.2	Aim of the test .....	27
7.7.3	Documents to be provided before test .....	28
7.7.4	Test method .....	28

7.7.5	Acceptance criteria .....	29
7.8	Test method for verification of generating set protections .....	29
7.8.1	General .....	29
7.8.2	Verification of generating set disconnection time from the grid .....	29
7.8.3	Verification of protection limits .....	30
8	Simulation-method-based assessment .....	31
8.1	General .....	31
8.2	Specification of model blocks .....	32
8.2.1	General .....	32
8.2.2	Engine and engine controller or governor block .....	32
8.2.3	AC generator block .....	33
8.2.4	Generating set controller block .....	33
8.2.5	Excitation controller (AVR) block .....	33
8.2.6	Exciter block .....	33
8.2.7	Protective devices block .....	33
8.2.8	Measurement transformer (if applicable) .....	34
8.3	Simulation for ISO performance class in standalone island operation .....	34
8.3.1	General .....	34
8.3.2	Model validation for standalone island mode .....	34
8.4	Simulation for generating sets used in grid connected applications .....	36
8.4.1	General .....	36
8.4.2	Requirements and methodologies for model validation .....	36
8.4.3	Model validation for different grid requirements .....	37
8.5	Assessment for generating set family .....	41
8.5.1	Methodology .....	41
8.5.2	Assessment for ISO performance class for family .....	41
8.5.3	Assessment for type test for family in grid parallel application .....	41
9	Acceptance test .....	42
9.1	General .....	42
9.2	Responsibility .....	42
9.3	Preparation .....	42
9.3.1	Provision of auxiliary personnel, test equipment and operating materials .....	42
9.3.2	Acceptance test preparation at the installation site .....	43
9.3.3	Acceptance test preparation at the manufacturer's site or facility .....	43
9.3.4	Preliminary safety checks on generating set prior to testing .....	43
9.4	Further details .....	43
9.5	Extent of acceptance test .....	44
9.5.1	General .....	44
9.5.2	Checks (C) .....	44
9.5.3	Measurements (M) .....	45
9.6	Accuracy of measurement equipment and acceptance test procedure .....	46
9.6.1	Measurement equipment accuracy .....	46
9.6.2	Warm-up time .....	46
9.6.3	Generating set load test duration .....	47
9.6.4	Performing acceptance tests at the manufacturer's works .....	47
9.6.5	Installation site acceptance test .....	47
9.7	Acceptance test report .....	48
9.7.1	General .....	48
9.7.2	General data .....	48
9.7.3	Additional measured data for acceptance test .....	50
	Annex A (informative) Test method using OVRT/UVRT test equipment .....	51
	Annex B (informative) Test method for frequency ride through requirements .....	58
	Annex C (informative) Example load step test report .....	63
	Bibliography .....	65