

DIN EN 15969-1:2011-11 (E)

Tanks for transport of dangerous goods - Digital interface for the data transfer between tank vehicle and with stationary facilities - Part 1: Protocol specification - Control, measurement and event data

Contents		Page
Foreword		4
Introduction		5
1	Scope	6
2	Normative references	6
3	Terms and definitions, abbreviations and conventions	6
3.1	Abbreviations	6
3.2	Terms and definitions	7
3.3	Conventions	8
4	Hardware interface	9
5	Basic protocol layer	9
5.1	FTL-frame (frame)	9
5.2	Frame flow (handshake)	10
5.3	Delay and timeout	16
5.4	CRC16 Checksum	16
6	Data protocol layer (FTL-data protocol)	17
6.1	Client (OBC) and server (TVE)	17
6.2	Syntax of data in datagrams	17
6.3	Nodes, subnodes, variables	17
6.4	Format identifiers	18
6.5	Types of variable values	20
6.6	Kinds of nodes	21
7	FTL-Data	22
7.1	General	22
7.2	Record and field types	22
7.3	Systemwide variables (subnode SYSTEM)	23
7.4	Variables related to global positioning system (subnode GPS)	26
7.5	Accessing a printer on TVE-side (subnode PRN)	26
7.6	Compartment information (subnode COMP)	30
7.7	Notification about changes (subnode NOTIFY)	31
7.8	Information about driver (subnode DRIVER)	32
7.9	Information about the vehicle (variable VEHICLE_ID)	33
7.10	Access to filesystem on TVE (subnode FS)	33
7.11	Auxiliary (subnode AUX)	39
7.12	Order management (subnode ORDER)	39
7.13	Goods and service database	43
7.14	FTL--logfile (subnodes LOG)	45
7.15	Required variables	73
7.16	NAK ID	73
8	Routing for multiple TVE	74
8.1	Purpose	74

8.2	Routing solution	74
8.3	Routing example	74
9	Communication with office	75
9.1	General	75
9.2	Simple file transfer	76
9.3	FTL over TCP/IP	77
10	Communication Examples	79
10.1	Examples for Basic Protocol Layer level	79
10.2	Examples for data protocol layer	81
Annex A (normative) Node tree		83
Annex B (normative) Test FTL		84
B.1	Overview	84
B.2	Basic Protocol Layer	84
B.2.1	Frame Tests	84
B.2.2	CRC-error	85
B.2.3	Delay and Timeout	85
B.3	Data Protocol Layer	86
B.3.1	Test of Toggling	86
B.3.2	Test of the FTL data layer	87
B.3.3	Test of the required FTL nodes	87
B.3.4	Optional System Subnodes	91
B.3.5	Optional Node Prn	92
B.3.6	Node Comp	94
B.4	Application Layer	100
B.4.1	Test of the L-File	100
B.4.2	Test of the LH-File	100
B.4.3	Test for the Filling of the NodeList	101
B.4.4	Sequence Test	101