DIN EN 13477-2:2021-12 (E)

Non-destructive testing - Acoustic emission testing - Equipment character isation - Part 2: Verification of operating characteristics

Contents

Page

European foreword 4

1 Scope 5

2 Normative references 5

3 Terms and definitions 5

4 Required test equipment and test signals 8
4.1 List of required equipment 8
4.2 Test signal waveforms 9
4.2.1 Continuous sine wave 9
4.2.2 Triangular-modulated sine wave burst signal 10
4.2.3 Sin2-modulated sine wave burst signal 12
4.2.4 Rectangular-modulated sine wave burst signal 13
4.2.5 Rectangular pulse 14
4.2.6 Repetitive signals 14
4.2.7 DC signal 15
4.2.8 Summary of test signals 15
4.3 Test block 15
4.4 Shielding test plate 15

5 Sensor verification 15
5.1 General 15
5.2 Intended purpose 16
5.3 Preparation of the report form and preliminary examination 16
5.4 Sensitivity verification 17
5.4.1 General 17
5.4.2 Test procedure 17
5.5 Verification of the electrical shield crosstalk 18
5.5.1 General 18
5.5.2 Procedure 22
5.6 Pre-amplifier verification of sensor-internal pre-amplifier 22

6 Pre-amplifier verification 23
6.1 Preparation of the report form and preliminary examination 23
6.2 Verification of DC consumption 24
6.2.1 General 24
6.2.2 Verifying a limit or a deviation 25
6.2.3 Procedure 25
6.3 Verification of the pre-amplifier characteristics 26
6.3.1 General 26
6.3.2 Gain verification 26
6.3.3 Bandwidth verification 28
6.3.4 Electronic noise verification 30
6.3.5 Dynamic range verification 32
6.3.6 Common mode rejection verification 35
6.3.7 Pulsing test 35

7 Acoustic emission signal processor verification 35
7.1 General 35

7.1.1 Overview ... 35
7.1.2 Preparation of the report form ... 38
7.2 Signal processor noise verification ... 39
7.2.1 General ... 39
7.2.2 Test procedure ... 40
7.3 Verification of RMS measurement and floating threshold functionality ... 41
7.3.1 General ... 41
7.3.2 Test procedure ... 43
7.4 Verification of the fixed detection threshold ... 43
7.4.1 General ... 43
7.4.2 Procedure for signal stimulation and data acquisition ... 45
7.4.3 Procedure for the data verification ... 45
7.5 Bandwidth and filter roll-off verification ... 45
7.5.1 General ... 45
7.5.2 Data needed for verification of bandwidth and roll-off verification ... 46
7.5.3 Procedure for signal stimulation and storage ... 46
7.5.4 Test procedure for bandwidth verification based on stored AE data ... 46
7.6 Burst signal parameter verification ... 47
7.6.1 General ... 47
7.6.2 Maximum amplitude verification ... 47
7.6.3 Duration verification ... 50
7.6.4 Rise-time verification ... 52
7.6.5 Ring-down count verification ... 54
7.6.6 Energy and signal strength verification ... 55

8 Verification of the system performance ... 58
8.1 External parametric input verification ... 58
8.1.1 General ... 58
8.1.2 Formulae for parametric input verification ... 59
8.1.3 Avoiding the use of a high-accuracy digital voltmeter (HADVM) ... 60
8.1.4 Report form preparation ... 60
8.1.5 Test procedure for signal stimulation and measurement for parametric input verification 61
8.1.6 Test procedure for parametric input data verification ... 62
8.2 Pulser verification ... 62
8.3 System acquisition rate verification ... 62
8.4 Delta t (t) measurement verification ... 63
8.5 Software verification ... 63

9 Test report ... 64

Annex A (informative) Report form for the sensor performance verification ... 65

Annex B (informative) Report form for the pre-amplifier performance verification ... 67

Annex C (informative) Report form for the acoustic emission signal processor verification ... 70

Annex D (informative) Report form for the external parametric input verification ... 75

Annex E (informative) List of designations ... 77

Bibliography ... 79