

ISO 8939:2025-10 (E)

Decommissioning of medical cyclotron

Contents		Page
Foreword		iv
Introduction		v
1	Scope	1
2	Normative references	1
3	Terms and definitions	1
4	Decommissioning planning for a medical cyclotron facility	3
4.1	General	3
4.2	Responsibilities	3
4.3	Decommissioning strategy	4
4.4	Decommissioning plan	4
4.5	Project management	5
4.6	Decommissioning activities	5
4.7	Safety assessment	5
4.7.1	Identification of relevant safety criteria	6
4.7.2	Risk assessment	6
4.8	Quality assurance programme	6
4.9	Radiation protection programme	7
4.10	Financial resources	8
4.11	Final radiological survey	8
4.12	Final decommissioning report	8
5	Activation evaluation	8
5.1	General	8
5.2	Activation level estimation method	9
5.2.1	Monte Carlo computer simulation	10
5.2.2	Measurement of activation	11
5.3	Nuclides of concern	11
6	Management of radioactive waste	12
6.1	General	12
6.2	Minimization of waste	13
6.3	Categorization and characterization of waste	13
6.4	Discharge control of liquid or airborne radioactive effluents	13
6.5	Onsite handling and processing of waste	13
6.6	Onsite storage of waste	14
6.7	Shipment of waste	14
Annex A (informative)	Measurement method for determining thermal neutron fluence rate on concrete surface	15
Annex B (informative)	Measurement method for determining specific activity using a scintillation survey meter	16
Bibliography		17