

ISO 22120:2026-08 (E)

Ships and marine technology - Specification for bunkering of methanol fuelled vessels

Contents

Page

Foreword	v
Introduction	vi
1 Scope	1
2 Normative references	1
3 Terms and definitions	1
4 Abbreviated terms	3
5 Transfer system provisions	4
5.1 Facility requirements	4
5.2 Transfer equipment	4
5.3 Safety equipment	6
5.3.1 Emergency release system	6
5.3.2 ESD system	7
5.3.3 Fire safety systems	7
5.3.4 Insulation connection	8
5.4 Auxiliary systems	8
5.4.1 Mooring equipment	8
5.4.2 Fenders	8
5.4.3 Communication systems	9
5.4.4 Measurement equipment	9
5.5 Maintenance	9
6 Risk assessments	9
6.1 Risk assessment approaches	9
6.1.1 General	9
6.1.2 Qualitative risk assessment (QualRA)	10
6.1.3 Quantitative risk assessment (QRA)	10
6.1.4 Risk assessment scope	11
6.2 Safety distance	11
6.2.1 General requirements	11
6.2.2 Hazardous areas	11
6.2.3 Safety zones	11
6.2.4 Security zones	12
7 Bunkering operational procedures	12
7.1 Pre-transfer stage	12
7.1.1 General	12
7.1.2 Compatibility assessments	12
7.1.3 Confirmation of bunkering conditions	13
7.1.4 Joint bunkering plans	15
7.1.5 Inerting and drying of the bunkering facility's lines	15
7.1.6 Connection of bunker systems	15
7.1.7 ERS	15
7.1.8 ESD connection testing	16
7.2 Transferring stage	16
7.2.1 General requirements	16

7.2.2	Inerting of bunkering lines	16
7.2.3	Bunkering operation	16
7.2.4	Monitoring	17
7.2.5	Repetitive checks	17
7.2.6	Topping up of the tank	17
7.2.7	Vapour management	17
7.3	Post-transfer stage	17
7.3.1	General	17
7.3.2	Inerting of bunkering lines	17
7.3.3	Checking after the bunkering	18
7.3.4	Disconnection of pipes	18
7.3.5	Disconnection of communications	18
7.3.6	Document handover	18
8	Safety protection	18
8.1	Personnel protection	18
8.1.1	Personal protective equipment (PPE)	18
8.2	Fire and explosion protection	19
8.2.1	Naked lights, smoking and personnel communication tools	19
8.2.2	Safety earthing of switchboards	19
8.2.3	Boilers and diesel engines	19
8.2.4	Portable electrical equipment	19
8.2.5	Marine radio equipment	20
8.2.6	Gas accumulation	20
8.3	Safety management	20
8.3.1	Openings of the living area	20
8.3.2	Safety zones	20
8.3.3	Security zones	21
8.3.4	Stop of bunkering operation	21
9	Personnel training	21
9.1	Vessel personnel training requirements	21
9.2	Additional training requirements for personnel involved in bunkering operations	22
9.2.1	General	22
9.2.2	Personnel providing methanol from port or mobile facilities training	22
10	Records and documentation	22
	Annex A (informative) Methanol bunker checklists	24
	Annex B (informative) Methanol Bunker Delivery Note (MBDN)	35
	Bibliography	36