

ISO/ASTM TR 52905:2023-06 (E)

Additive manufacturing of metals - Non-destructive testing and evaluation - Defect detection in parts

| Contents | | Page |
|-------------------|--|-------------|
| Foreword..... | | v |
| Introduction..... | | vi |
| 1 | Scope..... | 1 |
| 2 | Normative references..... | 1 |
| 3 | Terms and definitions..... | 1 |
| 4 | NDT potential for authentication and/or identification..... | 2 |
| 5 | List of abbreviated terms..... | 3 |
| 6 | Typical flaws/defects in AM..... | 4 |
| | 6.1 Flaw origins/causes..... | 4 |
| | 6.2 Flaw/defects classification..... | 4 |
| | 6.3 Defect classification strategies for AM..... | 12 |
| 7 | NDT standards review..... | 13 |
| | 7.1 Post-process NDT standards..... | 13 |
| | 7.1.1 ISO review..... | 13 |
| | 7.2 In-process NDT review..... | 15 |
| 8 | Standard selection structure for AM..... | 18 |
| 9 | NDT techniques potential for AM only defects..... | 19 |
| 10 | AM artefacts..... | 28 |
| | 10.1 Design..... | 28 |
| | 10.1.1 Star artefact..... | 28 |
| | 10.1.2 À la carte artefact..... | 34 |
| | 10.2 Manufacturing..... | 36 |
| | 10.2.1 Star artefact..... | 36 |
| | 10.2.2 À la carte artefact..... | 37 |
| 11 | NDT method trials and validation using star artefact..... | 38 |
| | 11.1 Experimental trials..... | 38 |
| | 11.1.1 X-ray Computed Tomography – XCT (MTC & GE & EWI)..... | 39 |
| | 11.1.2 Neutron Imaging — NI and Synchrotron radiation — SX (HZB & ESRF)..... | 43 |
| | 11.1.3 Thermography Testing — TT (University of Bath)..... | 50 |
| | 11.1.4 Resonant Ultrasound Spectroscopy methods — RUS..... | 59 |
| | 11.1.5 Ultrasonic testing — UT and Phase Array UT — PAUT (EWI and NIST and LNE)..... | 75 |
| | 11.1.6 Residual stress — RS (ILL)..... | 80 |
| 12 | Defect built validation star artefact (Cut-off MTC)..... | 85 |
| | 12.1 Summary of procedure by XCT..... | 85 |
| | 12.1.1 Apparatus..... | 86 |
| | 12.1.2 Significance of data/interpretation of results..... | 87 |
| | 12.2 Summary of procedure by metallography..... | 90 |
| | 12.2.1 Apparatus..... | 91 |
| | 12.2.2 Significance of data/Interpretation of results..... | 91 |
| | 12.3 Comments/observations..... | 93 |
| 13 | NDT trials for à la carte artefact..... | 94 |
| | 13.1 Summary of procedure..... | 94 |
| | 13.2 Apparatus..... | 94 |

| | | |
|----------------|--|------------|
| 13.3 | Significance of data/interpretation of results..... | 94 |
| 13.4 | Comments/observations | 97 |
| 14 | Summary of the trials findings by material..... | 97 |
| 15 | Main conclusions..... | 101 |
| Annex A | (informative) Causes and effects of defects in wire DED and PBF process | 104 |
| Annex B | (informative) Review of existing NDT standards for welding or casting for application of post build AM flaws..... | 106 |
| Annex C | (informative) Star artefacts using during the trials..... | 111 |
| Annex D | (informative) Summary of star artefact manufacturing and NDT technologies for trials..... | 115 |
| Annex E | (informative) XCT parameters and XCT set up used for inspection and validation..... | 118 |
| Annex F | (informative) Parameters and set up for Neutron Image (NI) and Synchrotron (Sx) inspection..... | 135 |
| Annex G | (informative) Set up for PT and SHT inspection..... | 141 |
| Annex H | (informative) Ultrasonic test..... | 144 |
| Annex I | (informative) Residual stress characterisation of Ti6Al4V by Neutron diffraction..... | 155 |
| | Bibliography..... | 157 |